

SURVEY & REMONUMENTATION

JAN 23 2001

LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners In: Located In: Corner Code #
Mason County

1. Public Land Survey

2. _____
T 17N R 17W I-6
T _____ R _____
T _____ R _____
3. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
4. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

1. Lot No. _____, Recorded Plat _____
3. Private Claims _____

FILED
AT 4:15 O'CLOCK P. M.
09 9 2000
MARGARET KOLASKI ELLIOTT
MASON COUNTY
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

Kenneth L. Ross in a field survey on September 18, 2000, Do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1/4 corner common to sections 14 and 15 of T17N, R17W

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO Hodgson 1838 Set qr. sec. post Beech 4" S53E 19 lks. (12.54') #1 Sugar 6" N17W 16 lks. (10.58') #2	Ross RLS 17634 LCRC & unrec. survey July 1974, L1 P196 Set 1/2" re-bar on E-W fen. 30" maple NW 54.78' #3 8" maple W. 34.93' #4 Dist. North to I-5 2608.52' Dist. South to I-7 2604.93'	Schulke RLS 30894 "found & Excepted existing iron as Public Land Corner" (I believe he meant accepted)
John Mitchell B1 P86 & 87 March 1880 1/4 post established by stone	Ross RLS 17634, 1990 & 1993 Unrecorded surveys "reset 1" pipe" No witnesses	
Griswold 1888 B1, P201 Nothing set		


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

found a 1" x 18" iron pipe 6" below the surface, 1' west of the centerline of a N-S gravel road.
Condition of the witnesses are as follows: 1, 2, and 3 are gone, 4 is in good condition

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

replaced the 1" x 18" iron pipe with a Harrison monument stamped "Mason County Monument RLS 17634". I accepted this as a careful and faithful reestablishment of the position of the original corner.
PP S80W 34.36' (set mag. nail North side) #5
36" Maple N30W 54.85' (Ex. 60d spike West side) #3
PP N17E 96.68' (set mag. nail West side) #6
SE corner concrete block foundation N45W 164.74' #7

Signed by Kenneth L. Ross Date 10-09-2000
Surveyor's Michigan License No. 17634



Approved by Peer Review Group on 10-05-2000
Kenneth L. Ross, County Representative [Signature]

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN, 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983