

MAR 08 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mason

(County)


Located In:

Corner Code #

- 1. Public Land Survey T 17N R 18W K-8  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

FILED

AT 11 O'CLOCK 9 M



MARY GOLDEN KOLASKI  
MASON COUNTY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Richard Hays, in a field survey on October 29, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-8 1/4 CORNER COMMON TO SECTIONS 23 & 24

- 1838:G.L.O. Set Post 1976:Mason Co. Rd. Comm. 1977:H. Fluharty Found
- 18" Maple S-06°-E 6 Links 1/2 Copper Rod in Mon. Box 1/2" Bar in Mon. Box
- 6" Beech S-15°-W 16 Links 27" Maple S-75°-E 147.17' (L.C.R.C. Liber 2, Pg 5,
- Power Pole S-80°-W 136.98' Liber 2, Pg 76, Liber 3,
- 1881:C.E. Mitchell Survey Conc. Mon. N-45°-E 46.73' Pg 23, Act 132 Liber 1,
- Identified by Govt. Markers. Pg 465)
- 16" Maple N-29°-E 147.10'
- 1967:K. Stephens Survey for Consumers Power-Set Corner. Power Pole S-80°-W 137.02'
- Poplar N-29°-E 66.98'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 1/4 CORNER COMMON TO SECTIONS 23 & 24


- 1993:Found 1/2" Iron Rod in Monument Box in Center Line Intersection.
- 27" Maple S-68°-E 147.11'
- 19" Poplar N-25°-E 66.95'
- Power Pole S-78°-W 137.13'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 1/4 CORNER COMMON TO SECTIONS 23 & 24

Replaced Found 1/2" Iron Rod with a Mason County Monument with 5/8" Re-Rod with cap stamped to identify Corner. This Monument is accepted as the best available evidence of the position of the Original Corner.

- 27" Maple S-68°-E 147.11'
- 19" Poplar N-25°-E 66.95'
- Power Pole S-78°-W 137.13'
- Concrete Monument on the ESE side of
- 4" Steel Post N-84°-W 331.72'
- In the Road Intersection



Signed by Richard Hays Date November 8, 1993  
 Surveyor's Michigan License No. 25847