



SURVEYOR	DRAWING NO.	DATE	IN FILE	DISTANCE TIES TO CORNER			
				NORTH	SOUTH	EAST	WEST
Mullett and Brookfield	GLO Notes	1837	yes	2640	2640	none	none
Peter Eastman	Book 1, page 25	1875	yes	2643.30			
John A. Mitchell	Book 1, page 39	1877	yes	2618.22	2666.40	2702.70	
C.E. Mitchell	Mason Co. Rd. Comm	1911	no	2628	2670		
Kenneth B. Stephens	C-70	1959	yes	1321.21 south to 1/16 corner			
Kenneth B. Stephens	C-67	1957	yes	1321.21 south to 1/16 corner			
Kenneth B. Stephens	M-99	1968	yes	2641.73	2641.72		5130.50
Kenneth L. Ross	B-113	1977	yes		2641.28		
Kenneth L. Ross	C-149	1977	yes		2641.28		
James T. Nordlund	S-77-51	1977	yes	2642.28'			2567.00
Kenneth L. Ross	unreadable	1979	yes	2642.97	2641.28	2692.10	
MDOT	Mason Co. Rd. Comm	Late 1970	no				2667.91
James T. Nordlund	S-86-29	1986	yes				2567.70
Kenneth L. Ross	25289S	1989	yes	2642.97			
Kenneth L. Ross	93317S	1993	yes	2642.69			2567.70
Kenneth L. Ross	94148S	1994	yes		2641.06		

Note: I found in my research for this corner that sometime between 1935 and 1977, a monument box was placed around this corner. All surveys researched refer to this corner as iron in monument box with no witnesses given.

MILE MEASUREMENTS FROM M-5 TO M-7 FOUND IN RESEARCH

SURVEYOR	DRAWING NO.	DATE	IN FILE	MILE MEASUREMENTS FROM M-5 TO M-7 FOUND IN RESEARCH
Mullett and Brookfield	GLO Notes	1837	yes	5280
Peter Eastman	Book 1, page 25	1875	yes	none
John A. Mitchell	Book 1, page 39	1877	yes	5284.62
C. E. Mitchell	Mason Co. Rd. Comm	1911	no	5298
MDOT	Mason Co. Rd. Comm	1935	no	5284.5
Kenneth B. Stephens	C-67	1957	yes	5284.86
Kenneth B. Stephens	C-70	1959	yes	5284.86
Kenneth B. Stephens	M-99	1968	yes	5283.45
Kenneth L. Ross	unreadable	1979	yes	5284.25

**SUMMARY OF THE LOCATION FOR CORNER M-6, T.17N., R.18W.,**

GLO set this corner in 1837, 2640 feet north of corner M-7 and 2640 feet South of Corner M-5. The Corner was set by Mullett and Brookfield.

Peter Eastman, 1875, (Book 1, Page 25) contracted survey work in both Section 7, T.17N., R.17W., and Section 13, T.17N., R.18W., He could not locate Corner M-5 (corner common to both section 7 and section 13). From his notes he ran the West line of Section 7, South from corner M-3, through corner M-4 and continued on to corner M-6. He then ran West along the South line of Section 7, from corner C-5, through corner B-5 and through M-5 on to L-5 (N 1/4 corner Section 13, T.17N., R.18W.,) and continued on to corner K-5 (NW corner Section 13) He then stated "set corner M-5 by intersection". At the location for corner M-6, he states on his survey the original witnesses by GLO, except he changed the do witness to a beech, no change in the diameter, bearings and distances given by GLO.

John A. Mitchell, 1877, (Book 1, page 39), contracted survey work in Section 18, T.17N., R.17W.. He states on his survey that at the corner M-5 location "established by Eastman" at the corner M-7 location "established by Eastman", at the corner M-6 location "Old witnesses trees" ( I cannot determine if he means the witnesses trees by Eastman or those of GLO). Distance from corner M-5 to corner M-6 differs by 25.04 feet shorter then that of Eastman. He then set the 1/16<sup>th</sup> corners along this line.

C. E. Mitchell, 1911, Mason County Road Commission Records, Contracted with the State to survey the road lying on the common line between section 13, T.17N., R.18W., and Section 18, T.17N., R.17W.,. He located corner M-5, M-6 and M-7 when completing this survey. His distance between corner M-5 and M-6 is 10 feet