

DEC 9 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

MASON (County)

Located in:

Corner Code #

FILED AT 2:57 O'CLOCK P M NOV 21 1998 MARY GOLDEN KOLASKI MASON COUNTY REGISTER OF DEEDS STAMP & FILE NUMBER

- 1. Public Land Survey T 18N R 16W C-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

I, Kenneth L. Ross, in a field survey on July 17 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-7 Section Corner for Sections 17, 18, 19 and 20, T18N-R16W.
1839, Sylvester Sibley, G.L.O. Set Wood Post
#1 Black Ash 14" S 77 W 10 lks. (6.60')
#2 Black Ash 14" N 65 E 27 lks. (17.82')
1902, R.O. Towns, Mason Co. Survey Found Stone for Section Corner @ 39.82 chs.
1954, Mason Co. Road Comm. (Land Corner Record) Stone & Crockery & Glass
#3 Old fence to the West
1973, Kenneth Ross, RLS# 17634 Found 3/4" Iron Pipe at the center-line of First & Darr Roads extended. (Liber 1 page 262)
#4 Road name sign N 50 E 52.90'
#5 Basswood 30' twin S 30 E 29.38'
#6 Basswood 24" S 50 E 49.82'
1997, Kenneth Ross, RLS# 17634, used 1/2" in Survey (file no. #97315s.)
#7 Willow 18" twin S 78 W 23.72'
#8 Cherry 9" N 27 W 55.21'
#9 Treated wood gate post S 08 E 34.00'
#10 Ash 28" S 48 E 49.82'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7 Section Corner for Sections 17, 18, 19 and 20, T18N-R16W.
I found 1/2" Iron Pipe, 14 1/2" long, over a wall-point, next to a stone (Towns), I found no evidence to dispute this location for the corner.
Condition of record witnesses are as follows; #1 Gone #2 Gone #3 Found old fence down
#4 Found in good condition #5 Found in good condition, tree is an Ash #6 Found in good condition, tree is an Ash.
#7 Found in good condition #8 Found in good condition
#9 Found in good condition #10 Found in good condition-same as #6

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7 Section Corner for Sections 17, 18, 19 and 20, T18N-R16W.
I replaced 1/2" Re-rod, in the exact location with a Harrison cast iron monument, (4" dia. Top, 18 1/2" long) stamped MASON COUNTY MONUMENT, I set the monument 0.4' below the ground, encased in concrete. This corner is accepted as a careful and faithful re-establishment of the position of the original corner.
Ext."BT" #7 Willow 18" twin S 78 W 23.72' (60d spike in NW side of tree)
Ext."BT" #8 Cherry 9" N 27 W 55.21' (60d spike in NE side of tree)
Ext."BT" #9 Gate Post treated wood 6" S 08 E 34.00' (60d spike in East side of post)
Ext."BT" #10 & 6 Ash 28" S 48 E 49.38' (60d spike in NE side of tree)

Signed by [Signature] Date Nov. 19 1998
Surveyor's Michigan License No. 17634

STATE OF MICHIGAN KENNETH L. ROSS LAND SURVEYOR No. 17634 FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 31, 1971

Peer Group Reviewed and Approved Date: 11-19-98 Kenneth L. Ross Mason County Surveyor