

DEC 29 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

MASON

(County)

Located In:

Corner Code #

1. Public Land Survey

T 18N R 16W

C-8

T R

T R

2. Property Controlling S T R

in Section S T R

3. Miscellaneous S T R

Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

10 O'CLOCK 27A

11

MARY G. MUMFORD

Register of Deeds Stamp & File Number

I, Kenneth L. Ross, in a field survey on July 23 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-8 1/4 Corner for Section 19 and 20, T18N-R16W.

1838, Sylvester Sibley, G.L.O.
Set Wood Post
#1 Beech 28" N 57 W 6 lks. (3.96')
#2 Beech 10" N 65 e 9 lks. (5.94')

1899, R. O. Towns, Mason Co. Surveyor
monument not given, show a distance of 40.17 chs.
(2651.22') from the SW corner, Section 20.
(book 2, page 91)

1997, Kenneth Ross, RLS #17634
Set 5/8" Re-Rod, at a split distance between controlling corners, in an existing fence line.
#3 Red Pine 7" N 83 W 18.80'
#4 Red Pine 16" N 40 E 25.45'
#5 Red Pine 14" N 77 E 40.70'
#6 Red Pine 6" S 43 W 44.40'
(file no. 97315s)

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8 1/4 Corner for Section 19 and 20, T18N-R16W.

On July 23, 1998, I found 5/8" re-rod set by me in previous Survey (97315s), found in old fence line running North - South. I found no evidence to dispute the location for this corner.

Condition of record witnesses are as follows; #1 Gone #2 Gone #3 Found in good condition
#4 Found in good condition #5 Found in good condition #6 Found in good condition

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


C-8 1/4 Corner for Section 19 and 20, T18N-R16W.

I placed an 3 1/2" aluminum cap, Stamped MASON COUNTY MONUMENT set on top of existing 5/8" re-rod, 24" in length, flush with the ground. This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

Ext. "BT" #3 Red Pine 7" N 83 W 18.80' (60d spike in NE side of tree)
Ext. "BT" #4 Red Pine 16" N 40 E 25.45' (60d spike in SE side of tree)
Ext. "BT" #5 Red Pine 14" N 77 E 40.70' (60d spike in SW side of tree)
Ext. "BT" #6 Red Pine 6" S 43 W 44.40' (60d spike in SE side of tree)

Signed by [Signature]
Surveyor's Michigan License No. 17634

Date Sept. 8, 1998 17634



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN. 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

Date 9-8-98
[Signature]
Mason County Surveyor