

DEC 29 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MASON (County)

Located In:

Corner Code #

- 1. Public Land Survey T 18N R 16W F-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

4. Lot No. Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number. Includes stamp: FILED 10 O'CLOCK 26A 11 1998 TARY DEN KOLASCI

I, Kenneth L. Ross, in a field survey on July 23, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-9 1/4 Corner for Sections 21 and 28, T18N-R16W.

1838, Sylvester Sibley, G.L.O. Used 20" Cedar for corner

J. E. Jones, no date (book 1, page 73) Identify by old Gov't marks on tree Gives distances of 2624.16' to SW cor. S-21 & 2618.88' to SE cor. S-21.

Mason Co. Road Comm. no date monument not given (Land Corner Record)

- #1 Cedar 30" N 53 W 38.10'
#2 Black Ash 16" S 54 W 35.3'
1991, Ted Weinert, RLS #19846 Found 3/8" Pin
#3 Ash 15" N 58 W 52.40'
#4 Cedar 12" S 50 W 48.38'
#5 Cedar 6" Due South 44.38' (Liber 3, Pg. 39)

- 1996, Ken Ross RLS #17634 Found 1/2" in Survey (file no. 98398s.
#6 Ash 18" N 60 W 52.39'
#7 Cedar 8" S 48 E 80.35'
#8 Cedar 10" S 52 W 48.18'
#9 Cedar 9" N 03 W 47.09'

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-9 1/4 Corner for Sections 21 and 28, T18N-R16W.

ON July 23, 1998, I found 1/2" re-rod in center-line of Conrad Road, used by local surveyors in the past. I found no evidence to dispute this location for the corner.

- Condition of record witnesses are as follows; #1 Gone #2 Gone #3 Found in good condition
#4 Found in good condition #5 Found stump #6 Found in good cond., same as #3
#7 Found in good condition #8 Found in good cond., same as #4 #9 Found in good condition

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9 1/4 Corner for Sections 21 and 28, T18N-R16W.

I replaced 1/2" re-rod, in the exact location, with a Harrison cast iron monument (4" dia. Top, 18 1/2" long), placed 0.5' below the road surface (gravel), this corner is accepted as a careful and faithful re-establishment of the position of the original corner.

- Ext. "BT" #6 Black Ash 20" N 60 W 52.39' (60d spike in SW side of tree)
Ext. "BT" #7 Cedar 9" S 48 E 80.35' (60d spike in SW side of tree)
Ext. "BT" #8 Cedar 10" S 52 W 48.18' (60d spike in NW side of tree)
Ext. "BT" #9 Cedar 8" N 03 W 47.09' (60d spike in West side of tree)

Signed by [Signature] Date Sept 8, 1998
Surveyor's Michigan License No. 17634

STATE OF MICHIGAN LAND SURVEYOR KENNETH E. ROSS No. 17634. Includes circular seal and text: FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1978 REVISED JAN. 1983 ADAPTED FOR WORD PROCESSING MARCH, 1993

9-8-98 [Signature]