

DEC 29 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION  
For corners in  
MASON  
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 18N R 16W G-6
- T R
- T R
- T R
- 2. Property Controlling in Section S T R
- S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

1970 FILED AT 10 O'CLOCK 16 M SEP 11 1998 MARY GOLDEN KOLASKI MASON COUNTY REGISTER OF DEEDS Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Kenneth L. Ross, in a field survey on August 25 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

|    |   |    |    |    |    |    |    |   |   |   |   |   |   |
|----|---|----|----|----|----|----|----|---|---|---|---|---|---|
| 1  | A | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
| 2  |   | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |   |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  |   | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |   |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  |   | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |   |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  |   | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |   |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 |   | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |   |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 |   | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |   |    |    |    |    |    |    |   |   |   |   |   |   |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-6 1/4 Corner for Sections 15 and 16, T18N-R16W.

1838, Sylvester Sibley, G.L.O.  
Set Wood Post  
#1 Beech 14" N 22 E 25 lks. (16.50')  
#2 Beech 10" S 61 W 14 lks. (9.24')

1976, Ken Ross, RLS #17634  
3/4" Pipe in monument box  
(file no. E-88, E-72, E-130, 92345s., 96294s.)

1972, N. C. Jones, RLS #02934  
Found Iron Pin inside 1 1/4" pipe, inside monument box.  
#3 Guy Pole N 47 E 51.33'  
#4 Ash 24" S 30 E 70.48'  
#5 Power Pole S 54 W 51.28'  
(liber 1 page 37)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6 1/4 Corner for Sections 15 and 16, T18N-R16W.

On August 25, 1998, I found a 3/4" Iron Pipe inside an 1 1/4" Iron Pipe, inside an existing monument box, at the center-line of U. S. 10. I found no evidence to dispute this location.

Condition of record witnesses are as follows: #1 Gone #2 Gone #3 gone #4 Found in good cond.  
#5 Found in good condition

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6 1/4 Corner for Sections 15 and 16, T18N-R16W.


I accepted 3/4" Iron pipe inside a 1 1/4" Iron pipe, inside a monument box, as a substantial marker for the corner. This Corner is accepted as a careful and faithful re-establishment of the position of the original corner.

- ext. "BT" #4 Ash 30" S 30 E 70.40' (set P.K. nail in SW side of tree)
- ext. "BT" #5 Power Pole S 54 W 51.10' (found 16p w/ shiner in SE side of pole)
- new "BT" #6 Power Pole N 43 E 51.81' (set P.K. nail in NW side of pole)
- new "BT" #7 SE corner of brick building Shell Station N 41 W 77.61'

Signed by Kenneth L. Ross Date Sept 3, 1998

Surveyor's Michigan License No. 17634

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
REVISED MAY 14, 1975  
REVISED JAN. 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993



Peer Group Reviewed and Approved  
Date: 7-8-98  
Kenneth L. Ross  
Mason County Surveyor