

DEC 29 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in _____ Located in: _____ Corner Code # _____
 MASON (County)

1. Public Land Survey T 18N R 16W G-8
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

10 - O'CLOCK 27A

11

Register of Deeds Stamp & File Number

I, Kenneth L. Ross, in a field survey on August 24 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-8 1/4 Corner for Sections 21 and 22, T18N-R16W.

1838, Sylvester Sibley, G.L.O.
 Set Wood Post
 #1 Hemlock 20" North 25 lks. (16.5')
 #2 Hemlock 8" S 24 E 30 lks. (19.80')

1983, Ken Ross, RLS #17634
 Found Iron in Monument Box
 (File no. E-122, E-156, 94119s. & 96398s.)

1880, James H. Jones, Mason Co. Surveyor
 Identify corner by old Gov't witness tree
 #3 Beech 12" N 59 W Distance ?
 (book 1 page 161)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8 1/4 Corner for Sections 21 and 22, T18N-R16W.

On August 24, 1998, I found a 3/4" Iron Rod, 30" long, inside an existing monument box at the center-line of Custer Road. This corner has been used frequently by local Surveyors. I found no evidence to dispute this location for the corner. Note the Top of monument box is frozen shut.

Condition of record witnesses are as follows; #1 Gone #2 Gone #3 Gone

C. Description of instrument for corner and accessories established to perpetuate locating the position of the corner:

G-8 1/4 Corner for Sections 21 and 22, T18N-R16W.

I remove old monument box, and place a Harrison cast iron monument in the exact location of the 3/4" Iron Rod, Harrison monument is stamped MASON COUNTY MONUMENT, and is placed flush with road surface, encased in concrete. This corner is accepted as a careful and faithful re-establishment of the position of the original corner. I took four new witnesses.

- #3 Power Pole N 82 W 35.16' (P.K. nail in South side of pole)
- #4 Power Pole S 09 W 238.76' (P.K. nail in NW side of pole)
- #5 Poplar 18" S 32 E 102.24' (P.K. nail in NE side of tree)
- #6 Poplar 22" N 42 E 68.44' (P.K. nail in NW side of tree)

Note; Measured reference distances from G-8 to G-9 at 2645.83 feet & from G-8 to G-7 at 2577.55 feet.

Signed by Ken Ross Date Sept 8-1998
 Surveyor's Michigan License No. 17634

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN. 20, 1971
 REVISOR REVISOR REVISOR
 REVISOR REVISOR REVISOR
 ADAPTED FOR WORD PROCESSING MARCH, 1983

For Grant, Reviewed
 and Approved

9-8-98