

DEC 29 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

MASON
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 18N R 16W G-9
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

FILED

10 O'CLOCK 26A

11

MAY 17 1998

Register of Deeds Stamp & File Number

I, Kenneth L. Ross, in a field survey on July 23 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-9 Section Corner for Sections 21, 22, 27 and 28, T18N-R16W.

- 1838, Sylvester Sibley, G.L.O.
Set Wood Post
#1 Sugar Maple 10" N 16 E 12 lks. (7.92')
#2 Sugar Maple 8" N 24 W 15 lks. (9.52')

1994, Ken Ross, RLS #17634
Found Iron in monument box
(file no. 94089s., 96398s.)

no date J. H. Jones, Mason Co. surveyor
monument not given, show a distance of 39.68 chs. (2618.88')
to the South 1/4 cor. Section 21, and a distance of
39.97 chs. (2638.02') to the South 1/4 Section 22.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9 Section Corner for Sections 21, 22, 27 and 28, T18N-R16W.

On August 24, 1998, I found a 3/4" Iron rod inside an existing monument box, frequently used by many surveyors. I found no evidence to dispute this location for the corner.

Condition of record witnesses are as follows: #1 Gone #2 Gone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9 Section Corner for Sections 21, 22, 27 and 28, T18N-R16W.

I replaced 3/4" Iron Rod, in the exact location with a 5/8" Re-Rod with an aluminum cap, stamped MASON COUNTY MONUMENT, inside the existing monument box, I encased the Re-Rod in concrete, this location is at the center-line of Custer Road. This corner is accepted as a careful and faithful re-establishment of the position of the original corner. I took four new witnesses.

- #3 Power Pole 8 43 W 49.17' (P.K. nail in NW side of pole)
- #4 Wood Guard Rail Post 6" x 8" N 55 W 51.80' (60d spike in the Top-center of post)
- #5 Wood Guard Rail Post 6" x 8" N 41 E 31.80' (60d spike in the Top-center of post)
- #6 Wood Guard Rail Post 6" x 8" S 48 E 32.85' (60d spike in the Top-center of post)

Note: I measured reference distances from G-9 to F-9 at 2654.32 feet & from G-9 to G-8 at 2645.83 feet

Signed by [Signature]

Date Sept 8-1998

Surveyor's Michigan License No. 17634

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1993

STATE OF MICHIGAN
KENNETH L. ROSS
LAND SURVEYOR
No. 17634

RECORDED
INDEXED
ADAPTED FOR WORD PROCESSING, MARCH, 1993

[Signature]