

DEC 29 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

MASON
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 18N R 16W H-7
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kenneth L. Ross, in a field survey on August 24 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
H-7 1/4 Corner for Sections 15 and 22, T18N-R16W.

1838, Sylvester Sibley, G.L.O.
Set Wood Post
#1 Beech 14" S 72 W 22 lks. (14.52')
#2 Beech 10" N 64 W 30 lks. (19.80')

1976, Ken Ross, RLS #17634
Found 3/4" Pipe in C-L of First St.
#3 Aspen 30" S 25 E 43.69'
#4 Power-Pole S 40 W 65.51'
Note: located a fence to the South
(file no. E-38, E-92, E-121, 92345s. & 94119s.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
H-7 1/4 Corner for Sections 15 and 22, T18N-R16W.

On August 24, 1998, I found a 3/4" Iron Pipe, 18" in length, next to a pointed wood stake, possible G.L.O., this corner is located in the center-line of First Street, at the end of pavement. I found no evidence to dispute this location for the corner.

Condition of record witnesses are as follows; #1 Gone #2 Gone #3 Found stump #4 Found cut off

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H-7 1/4 Corner for Sections 15 and 22, T18N-R16W.

I replaced 3/4" Iron Pipe, in the exact location, with a Harrison cast iron monument, stamped MASON COUNTY MONUMENT, I set the monument flush with pavement end, encased in concrete. This corner is accepted as a careful and faithful re-establishment of the position of the original corner. Note the wood stake was stuck in clean road fill, not likely original position G.L.O. probably used. I took four new witness.

- #5 Guide Pole N 45 W 28.60' (P.K. nail in NE side of pole)
- #6 Power Pole S 07 E 34.16' (P.K. nail in West side of pole)
- #7 Apple 24" S 62 W 163.22' (P.K. nail in SE side of tree)
- #8 Steel Post culvert marker N 77 E 65.04' (center of post)

Signed by [Signature] Date Sept 8, 1998
Surveyor's Michigan License No. 17634

FILED
AT 10 O'CLOCK 18 M
OF 11 1998
MARY GOLDEN KOJASKI
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

STATE OF MICHIGAN
KENNETH L. ROSS
LAND SURVEYOR
No. 17634
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1978
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993
Rec Group Reviewed
and by
Date: 9-8-98
[Signature]
Mason County