

RECORDED

DEC 2 9 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

MASON (County)

Located In:

Corner Code #

- 1. Public Land Survey T 18N R 16W I-6
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number. FILED AT 10 O'CLOCK 19 AM. MARY GOLDEN KOLASKA

I, Kenneth L. Ross, in a field survey on August 25 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-6 1/4 Corner for Sections 14 and 15, T18N-R16W. 1838, Sylvester Sibley, G.L.O. Set Wood Post #1 Sugar maple 10" S 10 E 16 lks. (10.56') #2 Sugar maple 8" N 23 W 11 lks. (7.26')

1976, Ken Ross RLS #17634 Found 3/4" Iron Pipe in monument box (file no. E-84, E-38, E-130,89225s., 92345s. 95199s.)

Grid with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6 1/4 Corner for Sections 14 and 15, T18N-R16W.

On August 25, 1998, I found a 1" Drift Pin inside an existing monument box, 2 feet North of the center-line of U.S. 10. I found no evidence to dispute this location for the corner.

Condition of record witnesses are as follows: #1 Gone #2 Gone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6 1/4 Corner for Sections 14 and 15, T18N-R16W.

I accepted 1" Drift pin in road monument box as a substantial marker for this corner, This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

I took four new witnesses.

- #3 Tele-phone junction box S 20 W 55.30' (top center)
#4 Stop Sign S 22 E 46.96' (center of post)
#5 "X" in Stone 6" x 12" N 35 W 64.10'
#6 Power-Pole N 29 E 61.65' (found 16d nail in SE side of pole)

Note: I measured reference distances from I-6 to I-5 at 2650.06 feet & from I-6 to I-7 at 2650.75 feet

Signed by [Signature] Date Sept. 8, 1998
Surveyor's Michigan License No. 17634

Professional seal for Kenneth L. Ross, Registered Land Surveyor, Michigan State Board of Land Surveyors. Includes text: FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971. REVISED MAY 14, 1976. ADAPTED FOR WORD PROCESSING MARCH, 1993.

Date 9-8-98 [Signature] Mason Court, Surveyor