

**SURVEY & REMONUMENTATION**

**FEB 08 2000**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

Owners in Mason County Located In: Corner Code #  
 Public Land Survey T 18N R 16W K-1  
 Property Controlling Section S T R  
 Miscellaneous S T R  
 Property in Sec. S T R

FILED  
 AT 10:34 O'CLOCK A. M.  
 NOV 10 1999  
 MARGARET KOLASKI ELLIOTT  
 MASON COUNTY  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

Plat No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

Kenneth L. Ross, in a field survey on September 10, 1999,  
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
 listed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Note: Not more than 4 corners, all in the same town and range, may be recorded  
 on this certificate.

Description of original monument and accessories and/or subsequent restoration:  
 Corner Common to Sections 1 and 2, T.18N., R.16W.,

- by Mullet and Brookfield, R.O. Towns, 1903, Book 1, page 100 and Book 4, page 116, "Located Cor. by Stone" No new Witnesses Given. Distance West to J-1, 2632.08' Distance South to K-2, 2638.02'
- by K.L. Ross, 1995, Act 132, Liber 457, page 790, States "existing Ross Iron", 9.22' East of Corner K-13, T.19N., R.16W., No new Witnesses Given.
- by Metcalf, 1896, Book 1, page 312 & 313, Survey of Section 1, States "Government witnesses down but ok" No new Witnesses Given. Distance East to L-1, 2632.08' Distance South to K-2, 2649.24'
- by Robert L. Wetherell, 1994, Act 132, Liber 447, page 593, Tied this cor. from K-13, T.19N., R.16W., East 9.22' No new witnesses given.
- by West to J-1, 2639.23' South to K-2, 2640.72'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner Common to Sections 1 and 2, T.18N., R.16W.,

and 4" x 25" re-rod and Surveyors Cap (unreadable), center-line of Reek Road to the North in the center-line of Decker Road to West and 5' South of the center-line of Decker Road to the East, There are Witnesses in the area, but I could find no recorded data on them. I could find no other evidence to dispute the location of this corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Corner Common to Sections 1 and 2, T.18N., R.16W.,

replaced the 4" re-rod and cap in the exact location with a Standard 3" Cast Iron Harrison Monument stamped "Mason County Monument" 1-foot below the surface of Decker Road, in the center-line of Reek Road to the North projected and center-line of Decker Road to the West projected and 5' South of the center-line of Decker Road to the East. This corner accepted as the best available evidence of the re-establishment of the position of the original corner.

- Existing 60d spike SE side of Guy Pole, S62°W, 40.28'
- Existing 60d spike SW side of P.P. N45°W, 46.51'
- Set 60d spike in NW side of Guy Pole, N53°E, 43.88'
- Existing 60d Nail in Top Guard Rail Post, S28°W, 12.56'
- K-13, T.19N., R.16W., East 9.22'

Note: GLO set this corner 16.5' East of Corner K-13, T.19N., R.16W., but, historically it has been used at 9.22'.

LIBER 4 PAGE 292



Signed by \_\_\_\_\_  
 Surveyor's Michigan License No. 17634

Date: Nov 4, 1999  
 Peer Group Reviewed and Approved  
 Date: 11-04-99  
 Kenneth L. Ross  
 Mason County Surveyor