

DEC 18 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

MASON (County)	Located In:	Corner Code --#
1. Public Land Survey	T 18 N R 17 W	H-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1970 FILED

AT 9:28 O'CLOCK a M

SEP 29 1995

MARY GOLDEN KOLASKI  
MASON COUNTY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Sammy S. Barnett, in a field survey on September 14, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-1 North 1/4 Corner for Section 3, T18N, R17W, on the township line

Note; This Corner was not set by original G.L.O. survey.

1902 R.O. Towns, MCS  
Identified corner as a stone  
no witnesses taken

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1 North 1/4 Corner for Section 3, T18N, R17W, on the township line

ON September 14, 1995, I found a 1/2" Re-rod 5' North of the center-line of Decker Road (gravel), just below the surface, I also found 3 old witness trees, that fit this location, but at this time I have not recovered a written record of this witnesses, I also found a concrete monument (plat type) South, @ 33.38 feet (Ross RLS Cap) and the South 1/4 Corner for Section 34, T19N, R17W, (1/2 Re-rod), I found no other evidence to dispute this location for the Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1 North 1/4 Corner for Section 3, T18N, R17W, on the township line

I replaced 1/2" Re-rod with a 5/8" Re-rod, 24 long, stamped MASON COUNTY MONUMENT, aluminum cap (2 1/2 in dia.) placed 0.5 feet below gravel road, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- OBT White Pine 14" S 42° E 43.38' (60d spike in SW side of tree)
- OBT White Pine 28" N 62° W 29.17' (60d spike in NE side of tree)
- OBT S. Maple 18" S 38° W 36.65' (60d spike in NW side of tree)
- S, Maple 7" S 26° W 51.43' (60d spike in SE side of tree)
- White Pine 16" N 18° W 50.37' (60d spike in NE side of tree)

Signed by Sammy S. Barnett

Peer Group Reviewed Date 9-28-95  
and Approved

Surveyor's Michigan License No. 16923

Date: 9-28-95  
Kenneth L. Ross  
Mason County Surveyor

