

# SURVEY & REMONUMENTATION

JAN 23 2001

## LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners In: Located In: Corner Code #  
Mason County

- |                                    |                         |       |       |
|------------------------------------|-------------------------|-------|-------|
| 1. Public Land Survey              | T 18N R 17W             | L-3   |       |
|                                    | T _____ R _____         | _____ | _____ |
|                                    | T _____ R _____         | _____ | _____ |
|                                    | T _____ R _____         | _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ | _____ |
|                                    | S _____ T _____ R _____ | _____ | _____ |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____ | _____ |
|                                    | S _____ T _____ R _____ | _____ | _____ |

FILED

AT 9:35 O'CLOCK A. M

AUG 17 2000

MARGARET KOLASKI ELLIOTT  
MASON COUNTY  
REGISTER OF DEEDS

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kenneth L. Ross in a field survey on June 8, 2000, Do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

$\frac{1}{4}$  corner common to sections 1 and 12 of T18N, R17W.

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO Sibley 1839 Set qr. post Beech 12 N81E 16 lks (10.56') #1 Beech 12 S61W 8 lks (5.28') #2	Ross RLS 17634 Unrecorded 1977 Ex. 1" pipe No witnesses taken  Bonney RLS 12016 L2, P57 & 60 Oct. 1978 30" Maple N10E 42.70' #4 8" Maple N30W 35.25' #5 Fence post South 37.25' #6	Slater RLS 7439 LCRC L2, P118, Aug. 1983 Fd. 1" iron bar flush with surface of Hansen Rd. 30" Maple N10E 42.70' #4 Cor. Fence post Due South 37.32' #6 8" Maple N30W 35.25' #5 9" Maple N40W 48.79' #7
---	--	---

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I found a 1" pipe in a monument box 1 ft. North of the centerline of E-W Road.  
Condition of the accessories are as follows: 1, 2, and 7 are gone. 4, 5, 6, and 7 are in good condition. I found no spikes or nails in 4, 5, 6 or 7.  
I found nothing to dispute the location of this corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I replaced the 1" pipe in the monument box with a 4" x 18 1/2" Harrison Monument stamped "Mason County Monument 17634" and accepted this as a careful and faithful reestablishment of the position of the original corner.

- P. Pole S65E 82.03' Set mag. nail NE side
- P. Pole S78W 131.17' Set mag. nail N side
- 10" Maple N26W 35.40' Set 60d spike E side #5
- 15" Tw. Maple N15E 42.93' Set 60d spike E side #4

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by [Signature] Date 8-10-2000  
Surveyor's Michigan License No. 17634

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28,

Approved by Peer Review Group on 8-10-2000  
Kenneth L. Ross, County Representative [Signature]

1971  
REVISED MAY 14, 1976  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993