

**SURVEY &
REMONUMENTATION**

DEC 18 1995

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MASON	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 18N R 17W	M-02
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

FILED

AT 3:34 O'CLOCK P M

SEP 15

MARY GOLDEN KOLASKI
MASON COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Sammy S. Barnett, in a field survey on September 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

<p>M-02 <u>East 1/4 Corner for Section 1, on Township Line, T18N, R17W.</u></p> <p><u>1839, Mullett & Brookfield, GLO</u> Set Wood Post</p> <p>#1 birch 7" S 59° W 28lks.(18.48')</p> <p>#2 Birch 7" N 77° W 14lks.(9.24')</p> <p><u>R.O. Towns, no date</u> Set Iron stake</p>	<p><u>1973, Anthony Slawinski, M.C.R.C.</u> Set 3/4" Iron in Monument Box</p> <p>#3 Maple 24" S 50° W 61.08'</p> <p>#4 Fence Post N 40° E 40.08'</p> <p>#5 Top of Guard Rail Post, N 35° W 35.54'</p> <p><u>1983, Lawrence Slater, M.D.O.T.</u></p>	<p>3/4" Iron in Monument Box #6 Power Pole Due West 69.92'</p> <p>#7 SE corner Culvert HDW S 87° E 21.65'</p> <p>#8 NE corner Culvert HDW N 49° E 26.20'</p> <p>#9 Maple 28" S 43° W, 60.20'</p>
---	---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-02 East 1/4 Corner for Section 1, on township Line, T18N, R17W.

On September 8, 1995, I found a 5/8" Re-rod in the center of a road monument box 1.0 feet West of the center-line of U.S. 31, due to resent road construction all of the record witnesses have been destroyed, I found no other evidence to dispute this location for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


M-02 East 1/4 Corner for Section 1, on township line, T18N, R17W.

I placed an aluminum cap, (2 1/2" in dia.), stamped MASON COUNTY MONUMENT over the top of the ^{EXISTING} ~~exciting~~ 5/8" re-rod, in the center of exciting monument box, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- Red Oak 10" N 30° W 116.04'(60d spike in SW side of tree)
- Power Pole N 88° W 106.28'(P.K. nail in South side of Pole)
- "X" in North side of a concrete Head Wall for HD Culvert N 82° E 53.17'
- "X" in North side of a concrete Head Wall for HD Culvert N 77° W 61.55'

Signed by Sammy S. Barnett Date 9-8-95

Surveyor's Michigan License No. 16923 Peer Group Reviewed and Approved



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 286 Date: 9-12-95
Kenneth L. Ross
Mason County Surveyor