

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

FILED

AT 11:10 O'CLOCK a M

OCT - 7 1994

**MARY GOLDEN KOLASKI
MASON COUNTY
REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

For corners in _____

MASON <small>(County)</small>	Located In:	Corner Code =#
1. Public Land Survey	T <u>19 N</u> R <u>15 W</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<u>Seg. 1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Sammy S. Barnett, in a field survey on September 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-13 SouthEast corner, Section 35, on the Township Line

1838, G.L.O., John Brink
Set wood post

#1 Beech 8" N 71° W 331k(21.78')
#2 Maple 4" N 35° E 201k(13.20')

1904 R.O. Towns, C.S.
Monument not given

1914, C.E. Mitchell
Monument - not given

1971, R.A. Griffin, P.S.
Did not find corner monument,
set by measured distance from
NW cor., Sec. 1, T18N, R15W, on
a straight line between NE & NW

of Section 1, T18N, R15W
Set 5" x 36" Conc. Monument
1990, John Schulke, P.S.
Found 10" dock spike, replaced
with 1" x 30" iron pipe

R.A. Griffins witnesses

#3 Maple 5" N 50° E 100.50'
#4 Tw. Maples 10"-10" N 38°
41.45'
#5 Center of brass cap monu
NE cor. Sec. 2, T18N, R15W
East 14.52'
#6 Pine Post 4" x 7' North
33.20'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 SouthEast corner, Section 35, on the Township Line

On September 20, 1994, I found 1" Iron Pipe North of center-line of Decker Road Found no other evidence to disbute this location for the corner.

NOTE; Did not recover R.A. Griffins concrete monument, might not have been set. witnesses is; #1 Gone #2 Gone #3 Found in good cond. #4 Found in good cond. #5 Found in good cond. #6 Found in good cond.


Condition of recorded

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 SouthEast corner, Section 35, on the Township Line

Replaced 1" Iron Pipe with a 5/8" Re-rod 24" in lenght with 2 1/2" aluminum cap, stamped Mason County Monument set 1 foot below Road surface, and is accepted as a careful and faithful reestablishment of the position of the original corner.

(OBT #3) Maple 5" N 50° E 100.50' (10" dock in SE side of tree)
(OBT #4) Tw. Maple 10"-10" N 38° W 41.45' (10" dock spike in SW side of tree)
Center of brass cap concrete monument East 14.58'
W Pine 9" N 28° E 48.78' (60d spike in NW side of tree)



Signed by Sammy S. Barnett Date 10/4/94
Surveyor's Michigan License No. 16923

Peer Group Review and Approval
Date: 10-5-94
Kenneth L. Ross
Mason County Surveyor

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, APR. 28, 11
REVISED MAY 14, 11
REVISED JAN., 11