

**SURVEY &  
REMONUMENTATION**

OCT 29 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
MASON COUNTY  
(County)

Located In:

Corner Code #

- |                                       |   |     |   |     |     |
|---------------------------------------|---|-----|---|-----|-----|
| 1. Public Land Survey                 | T | 19N | R | 16W | C-7 |
|                                       | T |     | R |     |     |
|                                       | T |     | R |     |     |
|                                       | T |     | R |     |     |
| 2. Property Controlling<br>in Section | S | T   | R |     |     |
|                                       | S | T   | R |     |     |
| 3. Miscellaneous<br>Property in Sec.  | S | T   | R |     |     |
|                                       | S | T   | R |     |     |

FILED	
AT 9:14 O'CLOCK	a M
OCT 15 1996	
MARY GOLDEN KOLASKI MASON COUNTY REGISTER OF DEEDS	
Register of Deeds Stamp & File Number	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, THEODORE H. WEINERT, in a field survey on SEPTEMBER 21, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

Sylvester Sibley subdivided the Township in 1838 and 1839. Set Post at this location 80 Chains North of the SE Corner. Witnesses Taken: (1) Tamarack, N 63° W, 8 links  
(2) Cedar, 16", S 11° E, 30 links

In November, 1899, Book 3 pages 16 and 17, R.O. Towns Completed a survey of Section 18, and referred to this corner as identified by stake from former surveyor and Tamarack is down (referring to GLO) Witness taken, (3) Pine, 24", S32°E, 44 links. In May, 1990, Kenneth L. Ross, RLS, Completed a survey in Section 19, and tied this corner, Stated " found 1/2" iron by Hepworth, RLS,". Witnesses given: (4) 18" Maple, S80°E, 42.86', (5) 10" cherry, S50°W, 29.23', (6) 12" Maple, N45°W, 26.92', Trace of fence to east, in East Wheel Track of two track Road. Distance West to N 1/4 Corner 2651.93', distance South to E 1/4 Corner, 2597.80'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

On September 21, 1996 I found the 1/2" iron as described in "A" above. I cross pinned the existing iron and pulled. I searched the area and found no other evidence to dispute the location of this corner. Witnesses (4), (5) and (6) are standing and in good condition. Witness (5) is starting to die. The 1/2" iron is 4' long.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I replaced the existing 1/2" iron, in the exact location with a Standard Mason County Monument, placed flush with the surface of the ground, and accepted as a careful and faithful reestablishment of the position of the original corner.

- Witnesses Taken:
- (4) Spike in 24" Double Maple, S80°E, 42.86'
  - (5) Spike in 10" Cherry, S50°W, 29.23'
  - (6) Spike in 15" Maple, N45°W, 26.92'
  - Spike in 8" Maple, S85°E, 23.26'
  - Spike in 12" Maple, N85°W, 25.68'
  - 1.0' East of East Wheel Track of Two Track Road
  - 150' plus or minus North of North edge of low area
  - 25' plus or minus South of South edge of low area

Signed by Theodore H. Weinert

Date 9/30/96

Surveyor's Michigan License No. 19846

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993

Peer Group Reviewed  
and Approved  
Date: 9-30-96  
Kenneth L. Ross  
Mason County Surveyor

LIBER

4 PAGE

82