

**SURVEY & REMONUMENTATION**

OCT 29 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
MASON COUNTY  
(County)

Located In:

Corner Code #

FILED	
AT 9:14	O'CLOCK a M
OCT 15 1996	
MARY GOLDEN KOLASKI MASON COUNTY REGISTER OF DEEDS	
Register of Deeds Stamp & File Number	

- |                                    |             |       |
|------------------------------------|-------------|-------|
| 1. Public Land Survey              | T 19N R 16W | C-9   |
|                                    | T _____     | _____ |
|                                    | T _____     | _____ |
|                                    | T _____     | _____ |
| 2. Property Controlling in Section | S _____     | _____ |
|                                    | S _____     | _____ |
| 3. Miscellaneous Property in Sec.  | S _____     | _____ |
|                                    | S _____     | _____ |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, THEODORE H. WEINERT, in a field survey on SEPTEMBER 18, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**  
Subdivision of the township was completed by Sylvester Sibley, in 1938 to 1939. Ran East between Sections 19 and 30 first taking Witnesses to this Corner.  
Witnesses Taken: (1) Beech, 16", S 40° E, 28 links  
(2) do, 6", N 31° E, 19 links.  
November 1904 R.O. Towns completed a survey of Section 30, tying in to this Corner, found 2" Pipe. Distance West to N ¼ Corner, 2616.64'. Witnesses Taken: (3) Pine Stump, 19° 30' W, 82 links Recorded Book 2, pages 186 and 187. Kenneth L. Ross, RLS completed a survey in Section 30 tying in to this corner stating from Towns Survey at this location. (1904). No Witnesses Taken. Measured Distance by Ross, to West, 2619.60' to N ¼ Corner Section 30. (4/16/79) No other data found during research of this corner.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
On September 18, 1996, I found the 2" pipe as described by R. O. Towns and Kenneth L. Ross, RLS. Witnesses (1), (2) and (3) have been destroyed. I searched for the Pine Stump as described by R.O. Towns, But could not locate. Fit Distances as described by Kenneth L. Ross, RLS, West and North. I could find no other evidence to dispute location of this corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
I placed a Standard Mason County Monument (5/8" X 2' Re-rod and standard cap) inside the 2" pipe, 8" below the surface of the gravel road, and is accepted as a careful and faithful reestablishment of the position of the original corner. Witnesses Taken:  
Spike in REP. S42°W, 40.35'  
Spike in North side of Five 3" to 8" Maple Clump, N55°W, 25.97'  
Spike in North side of Five 4" to 6" Maple Clump, N25°W, 38.81'  
Spike in 18" Maple, N35°E, 63.35'  
Spike in Small Maple Clump, S79°E, 26.10'  
Fence Corner Post, 33 feet East and 35 feet North of Corner, Fence North and East from corner post.  
1 foot east of Road North-South center-line

Signed by *Therese A. West*

Date 9/30/96

Surveyor's Michigan License No. 19846

Peer Group Reviewed and Approved  
Date: 9-30-96  
*Kenneth L. Ross*  
Mason County Surveyor

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993