

SURVEY & REMONUMENTATION

OCT 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MASON (County)

Located In:

Corner Code #:

- 1. Public Land Survey T 19 N R 16 W E-07
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

FILED

AT 11:46 O'CLOCK a M

AUG 14 1996

MARY GOLDEN KOLASKI
MASON COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Sammy S. Barnett, in a field survey on July 11, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-07 Section Corner for Sections 16, 17, 20 and 21, T19N, R16W.

Sylvester Sibley, 1838, G.L.O.

Set Wood Post

#1 Black Ash 14" N05°E 181ks.(11.88')

#2 Elm 14" S04°W 201ks.(13.20')

R.O. Towns, MCS, 1902

Iron

no new witnesses

Randy Hepworth, RLS#26457, 1985

Found 1 1/2" Pipe, @ C/L of old Roads

#3 Maple 12" N23°E 33.00'

#4 Maple clp. 12" S60°E 22.95'

#5 Maple clp. 12" N70°W 55.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-07 Section Corner for Section 16, 17, 20 and 21, T19N, R16W.

On July 11, I found a 1 1/2" Iron Pipe, at the intersection of two-track undeveloped Tuttle & Millerton Road. I found no evidence to disputed this location for the corner.

Condition of recorded witnesses are;

#1 Gone

#2 Gone

#3 Found in good condition

#4 Found in good condition

#5 Found in good condition

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-07 Section Corner for Sections 16, 17, 20, and 21, T19N, R16W.

I set a Standard Mason County Monument inside the existing iron pipe, flush with the surface of the ground, and is accepted as a careful and faithful reestablishment of the position of the original

(ext. BT #3) Maple 15" N 23° E 33.00' (60d spike in SE side of tree)

(ext. BT #4) Maple clp. 14" S 60° E 22.95' (60d spike in NE side of tree)

(ext. BT #5) Maple clp. 14" N 70° W 55.50' (60d spike in SW side of tree)

Maple 7" N 31° W 39.76' (60d spike in NE side of tree)

Signed by Sammy S. Barnett

Surveyor's Michigan License No. 16923

Peer Group Reviewed and Approved

Date: 8-12-96
Kenneth L. Ross
Mason County Surveyor

Date 8-12-96



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983