

SURVEY & REMONUMENTATION

OCT 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MASON
(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|-----------------------------|-------|
| 1. Public Land Survey | T <u>19</u> N R <u>16</u> W | E-09 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

FILED

AT 11:48 O'CLOCK a M

AUG 14 1996

MARY GOLDEN KOLASKI
MASON COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Sammy S. Barnett, in a field survey on July 11, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-09 Section Corner for Section 20, 21, 28 and 29, T19N, R16W.

Sylvester Sibley, 1838, G.L.O.

Set Wood Post

#1 Hemlock 16" S32°E 331ks.(21.78')

#2 Hemlock 14" N31°W 171ks.(11.22')

R.O. Towns, MCS, 1902

Stone

no witnesses

Ken Stephens, no date

Stone & 2" Iron

#3 Tele-Pole NW 80.90'

#4 wood stake West 23.20'

#5 Tele-Pole SE 36.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-09 Section Corner for Sections 20, 21, 28 and 29, T19N, R16W.

On July 11, I found a 1/2" x 18" Re-rod at the intersection of Tuttle & Dewey Roads, also found Stone under Re-rod, found no evidence to dispute this location for the corner.

Condition of recorded witnesses are;

- #1 gone
- #2 gone
- #3 gone
- #4 gone
- #5 gone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-09 Section corner for Sections 20, 21, 28 and 29, T19N, R16W.

I replaced 1/2" Re-rod. in the exact location, with a Standard Mason County Monument, 1.0 foot below the road surface (gravel), and is accepted as a careful and faithful reestablishment of the position of the original corner.

Tele-Junc. Box (top-center) S 42° E 42.13'

P. K. Nail due South in pavement 34.83'

Steel Post (top-center) N 10° W 75.65'

Steel Post (top-center) N 20° E 77.70'

Signed by Sammy S. Barnett

Surveyor's Michigan License No. 16923

Peer Group Review Date 8-17-96

and Approved Date: 8-13-96

Kenneth L. Bots
Mason County Surveyor



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1987