

**SURVEY & REMONUMENTATION**

OCT 29 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Mason County  
(County)

Located In:

Corner Code #

|  |     |
|--|-----|
| FILED  |     |
| AT 9:30 O'CLOCK  | 9 M |
| OCT 15 1996  |     |
| MARY GOLDEN KOLASKI<br>MASON COUNTY<br>REGISTER OF DEEDS |     |

Register of Deeds Stamp & File Number

|                                    |             |      |
|------------------------------------|-------------|------|
| 1. Public Land Survey              | T 19N R 17W | F-13 |
|                                    | T R         |      |
|                                    | T R         |      |
|                                    | T R         |      |
| 2. Property Controlling in Section | S T R       |      |
|                                    | S T R       |      |
| 3. Miscellaneous Property in Sec.  | S T R       |      |
|                                    | S T R       |      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

|    |    |    |    |    |    |    |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 1  | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

I, Theodore H. Weinert, in a field survey on September 21, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**  
Mullet and Brookfield ran the original Township lines in 1837 and 1838, Stating "set quarter Section post". Witnesses given: (1) Beech, 14", N33°W, 44 links, (2) Do, 6", N48°E, 29 links. On May 9, 1892, John A. Mitchell, Surveyed the North West One-Quarter of Section 33 Stated "Quarter Post 43 links West of Quarter Post for Section 4, T.18N., R.17W. No Witnesses Given. Kenneth L. Ross, RLS, Completed a survey of Section 4, T.18N., R.17W., in 1977 and set this corner. Stated "Set 1" pipe with cap. Fence to North, 28.35' West of N ¼ corner of Section 4". (Note GLO was 28.39', (43 links). Witnesses given: (3) 6" Red Pine, S10°E, 39.84', (4) 4" Maple, N10°E, 32.63', (5) 36" Maple, S75°E, 89.14'. Not other data found during research of this corner.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
On September 21, 1996, I found the 1" pipe with cap as described in "A" above. I crossed pinned this existing iron and pulled it. I searched for any other iron in the area. Found no other evidence to dispute the location of this corner. Witnesses (1), (2), (3), (4) have been destroyed. Witness (5) is standing and in good condition.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
I replaced the existing 1" iron pipe, in the exact location with a Standard Mason County Monument, placed 1.0' below the gravel surface of the road, and accepted as a careful and faithful reestablishment of the position of the original corner. Witnesses Taken:  
(5) Spike in 40" Maple, S71°E, 89.16'  
Spike in Rail Road Tie, Gate Post, Due South, 38.74'  
Spike in 12" Red Pine, S53°W, 57.28'  
Spike in 12" Cherry, N72°W, 79.36'  
Spike in 6" Maple, N40°E, 25.56'  
N ¼ Corner Section 4, T.18N., R.17W., East, 28.35'

Signed by Theodore H. Weinert  
Surveyor's Michigan License No 19846

Date 9/30/96

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISD MAY 14, 197  
REVISD JAN., 198  
ADAPTED FOR WORD PROCESSING MARCH, 199  
Peer Group Reviewed and Approved  
Date: 9-30-96  
Kenneth L. Ross  
Mason County Surveyor