

DEC 29 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION Mason (County)

Located In:

Corner Code #

Register of Deeds Stamp & File Number. Filed at 3:08 O'CLOCK P.M. NOV 2 1998 MARY GOLDEN KOLASKI MASON COUNTY REGISTER OF DEEDS

- 1. Public Land Survey T 19N R 17W K-9
2. Property Controlling in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. Recorded Plat
5. Private Claims

I, Kenneth L. Ross, in a field survey on October 24, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GOVERNMENT SURVEY Section Survey by Sylvester Silbely 1838 to 1839, Set Post (1) Beech, 16", N56°E, 25.74' (2) Beech, 16", S24°W, 15.84'

Kenneth L. Ross, Survey unrecorded, File H-209, 1974 Found 1" Pipe North side of road (3) 16" Maple, N85°E, 104.34' (4) 16" Maple, S35°W, 68.05' (5) 12" Tw Cherry, N80°W, 3.88'

H.B. Johnson, 1894, Book 1, Page 274 Mason County Records. States Section corner, both witness trees standing. No New Witnesses

Randolph Hepworth, LCRC, Liber 3, Page 34 Mason County Records, 1989

Witness (5) above, distance 3.81' (6) 6" Maple, 358°az, 10.00' (7) 20" Tr. Maple, 219°az, 68.35' (8) 30" Maple, 92°az, 104.19'

Kenneth L. Ross, 1997, Survey, unrecorded. File No. 973245 Fd. 1" Pipe, 8" below road surface, 10' North of c/l Dewey Road. (9) P.P. S05°W, 41.92' (10) Triple Maple, 10-10-18", N60°W, 83.50' (11) 12" Maple, N60°E, 88.80' (7) 20" Maple, S38°W, 68.45'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" X 18" Pipe, 12" below the road surface on North side of Road.


Condition of record witnesses as follows: (1) gone, (2) gone, (3) gone, (4) gone, (5) gone, (6) gone, (7) good condition, (8) good condition, (9) good condition, (10) good condition, (11) gone,

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1" X 18" pipe in the exact location with a 4" X 20" Harrison Monument stamped "Mason County Monument", 12" below the road surface. This corner is accepted as a careful and faithful re-establishment of the location of the original corner.

- Ex "B.T." (7) 20" Maple, S 38°W, 68.45 feet, (60d spike SE side)
Ex "B.T." (8) 30" Maple, S 88° E, 104.19 feet, (60d spike North side)
Ex "B.P." (9) P.P. S 05°W, 41.91 feet, (60d spike East side)
Ex "B.T." (10) Triple Maple 10-10-18, N60°W, 83.50 feet, (60d spike SW side)
(12) Hepworth iron and cap North 33.00 feet

Signed by [Signature] Date 11-19-98
Surveyor's Michigan License No. 17634



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN. 1983 ADAPTED FOR WORD PROCESSING MARCH, 1993

Approved by Peer Review Group On 11-19-98
Kenneth L. Ross, County Representative [Signature]