

MAR 16 1998

LAND CORNER RECORDATION CERTIFICATE

SECTION FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 20N N. S., R. 15W E. W.	A1
2. PROPERTY CONTROLLING IN SECTION	T. N. S., R. E. W.	Seg. 2
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

FILED  
AT 10:10 O'CLOCK a

**NOV 17 1994**

MARY GOLDEN KOLASKI  
MASON COUNTY  
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram--over) were, in a field survey on October 30 1994, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**Closing section corner common to sec. 1 of T20N R16W and sec. 6 of T20N R15W**

1838 survey by Mullett & Brookfield Set Wood Post #1 W.Pine 14 S44E (no distance given) Only one bearing tree was mentioned	1942 search by R.C. Townsend USFS Fd. conc. block monu. lying on ground No witnesses taken as he was not sure if this is the corner.	1972 survey by Robert A. Griffin #13584 Searched for but did not find the Mitchell corner. Set a 5" sq. by 36" long conc. monu. w/ brass cap. #4 W.Oak 5 S28E 67.92 feet #5 B.Oak 6 S9E 64.34 feet #6 P.Post 4 South 32.99 feet #7 W.Oak 5 S29W 78.11 feet
1918 survey by C.E. Mitchell No monument mentioned #2 Oak 6 N54 1/2 W 63 links #3 Oak 5 S49W 77 links		

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
I found the 5" square by 36" long concrete monument w/ brass cap by Griffin buried 8" beneath the surface and 7 feet North of the centerline of the E-W road. Witnesses 1 through 3 and 6 are gone. Witnesses 4, 5 and 7 are in good condition. Liber 1 Page 77 by Griffin documents the history of this corner. Griffin set this corner 80 chains east of the NW corner of section 1 and on a straight line between the SW and S1/4 corner of section 32 T21N R15W according to the GLO calls. The remainder of the GLO calls do not aid in determining this location. I could find no conflicting information that would lead to another location. I therefore accept the found monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**Closing section corner common to sec. 1 of T20N R16W and sec. 6 of T20N R15W**  
Monu. The 5" square by 36" long concrete monu. with 3" brass disk was left in place.  
Witnesses:  
Rebar 5/8" x 24" N34W 69.54 feet  
Rebar 5/8" x 24" N39E 67.58 feet  
W.Oak 8 S28E 67.92 feet (#4)  
B.Oak 11 S9E 64.38 feet (#5)  
W.Oak 9 S29W 78.11 feet (#7)



SIGNED BY Patrick R. Leemon DATE October 30, 1994  
SURVEYOR'S MICHIGAN REGISTRATION NO. 31595 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ LIBER 3 PAGE 196

Peer Group Reviewed and Approved  
Date: 11/16/94  
Kenneth L. Ross  
Mason County Surveyor