

DEC 18 1995

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	20N N. 15W E. S., R. W.	K4
2. PROPERTY CONTROLLING IN SECTION _____ T. _____	N. E. S., R. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____	N. E. S., R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

FILED

AT 10:22 O'CLOCK a M

OCT 18 1995

MARY GOLDEN KOLASKI
MASON COUNTY
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 15, 1995, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

1/4 corner common to sections 11 and 12 of T20N R15W

1839 survey by John Brink Set Wood Post, (1) W.Pine 16 N40E 19 links, (2) W.Pine 18 N20W 35 links
 1904 survey by Robert O. Towns No monument given, NW 12 North 2691.48 ft., SW 12 South 2618.88 ft.
 1975 survey by Nordlund and Assoc. NW 12 N0-48-33E 2698.92 ft., SW 12 S0-22-27E 2626.12 ft.
 1984 survey by Dennis W. Dunlap #21759 Used a 1 1/2"x60" Iron Pipe, (3) W.Oak 7 S60E 8.1 ft., (4) B.Oak 5 S89W 25.9 ft., (5) B.Oak 7 N44W 45.0 ft., NW 12 N1-27-04W 2697.87 ft., SW 12 S2-37-09E 2623.68 ft.
 1985 survey by Robert A. Griffin #13584 LCRC Liber 2 Page 280, Replaced the Iron Pipe with a 1 1/4"x30" Iron Pipe with a 1/2"x18" rebar w/ RLS cap cemented inside, (3) W.Oak 10 S54E 8.21 ft., (4) R.Oak 8 S86W 25.90 ft., (5) R.Oak 10 N48W 45.89 ft.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the 1 1/4" Iron Pipe with 1/2" rebar and RLS cap by Griffin near the northeast corner of a marsh and the southwest corner of a clearcut. Witnesses 1 and 2 are gone. Witness 3 through 5 are in good condition. I could find no conflicting information that would lead to another location. This monument is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/4 corner common to sections 11 and 12 of T20N R15W

Monu. The 1 1/4" Iron Pipe w/ 1/2" rebar and RLS cap was left in place.

Witnesses:

- 60d nail in the southwest side of a W.Oak 11 S61E 8.12 ft. (3)
- 60d nail in the north side of a R.Oak 10 S84W 25.90 ft. (4)
- 60d nail in the southwest side of a R.Oak 14 N47W 45.90 ft. (5)
- 60d nail in the east side of a R.Maple 7 N34E 28.70 ft.
- Fiberglass Post East 0.70 ft.

Peer Group Reviewed and Approved
 Date: 10-22-95
 Kenneth L. Ross
 Mason County Surveyor

SIGNED BY Patrick R. Leemon DATE October 15, 1995

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



LIBER 3 PAGE 315

SURVEYOR'S MICHIGAN REGISTRATION NO. _____