

DEC 18 1995  
LAND CORNER RECORDATION CERTIFICATE  
COMMISSION FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ 20N N. 15W S., R. _____ E. W.	M1 (South)
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

FILED

AT 10:25 O'CLOCK am

OCT 18 1995

MARY GOLDEN KOLASKI  
MASON COUNTY  
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 15, 1995, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**Meander Corner common to section 1 of T20N R15W and section 6 of T20N R14W on the South side of Lake of the Woods**

- 1838 survey by Mullett & Brookfield Set Post, (1) Cedar 10 S42W 45 links, (2) Cedar 8 S19E 41 links
- 1913 survey by George Johnson Oak Stake, (3) Tw.W.Oak 5 S51W 32 ft.
- 1932 survey by W. H. Read Mason Co. Surveyor Meander Post, (4) Maple 12 S83E 46.4 ft., (5) Cedar 9 S22E 39.7 ft., E1/4 1 South 3775 ft.
- 1952 survey by Charles Dodt #2174 Fd. MC, MC on East side of Lake of the Woods is N48-51E 398.1 ft.
- 1972 survey by Theodore H. Weinert #19846 Fd. 1" Iron Pipe with Cedar Post scribed M.C., no witnesses given, W1/4 6 S4-46-37E 3776.48 ft., Comp. between South MC and East MC N41-10E 420.31 ft.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the 1" Iron Pipe used by Read in good condition and firmly set flush with the ground, 20 feet south of the south edge of Lake of the Woods and 230 feet more or less East of a cabin. Witnesses 1 through 3 are gone. Witness 4 is alive but dying and witness 5 is a stump. I could find no conflicting information that would lead to another location. This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**Meander Corner common to section 1 of T20N R15W and section 6 of T20N R14W on the South side of Lake of the Woods**

Monu. I set a 5/8"x60" rebar with aluminum cap inside the 1" iron pipe.

Witnesses:

- 60d nail in the south side of a R.Maple 17 S85E 46.53 ft. (#4)
- 60d nail in the south side of a B.Ash 8 N89E 5.20 ft.
- 60d nail in the west side of a B.Ash 12 S3W 12.78 ft.
- Fiberglass Post North 0.50 ft.
- 60d nail in the north side of a R.Maple 11 S67W 31.44 ft.

SIGNED BY Patrick R. Leemon DATE October 15, 1995

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

Date: 10-17-95  
Kenneth L. Ross  
Mason County Surveyor

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_



LIBER 3 PAGE 320