

DEC 18 1995

LAND CORNER RECORDATION CERTIFICATE
COMMISSION FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	20N N. 15W E. T. S., R. W.	M2
2. PROPERTY CONTROLLING IN SECTION _____	N. E. T. S., R. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	N. E. T. S., R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

FILED

AT 10:24 O'CLOCK a.m.

OCT 18 1995

MARY GOLDEN KOLASKI
MASON COUNTY
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 15, 1995, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

1/4 corner common to section 1 of T20N R15W and section 6 of T20N R14W
 1838 survey by Mullett & Brookfield Set Post, (1) Beech 10 N30W 15 links, (2) W.Pine 18 S44W 11 links
 1913 survey by George H. Johnson #504 No monument given, (3) W.Pine 14 N58E 87 ft.,
 (4) W.Pine Stp. 40 N68W 59 ft., SW 6 South 2640 ft.
 1932 survey by W. H. Read Mason Co. Surveyor (5) N.Pine 10 N36E 27.15 ft., (6) N.Pine 9 N41-30W 36.5 ft., MC on the side of Lake of the Woods is North 3775.0 ft., SE 1 South 2629.3 ft.
 1969 survey by Robert A. Griffin #13584 Fd. 1" Iron Pipe, (5) R.Pine 21 N33E 27.63 ft., (7) R.Pine 8 S70E 30.84 ft., (8) R.Pine 4 S33W 40.60 ft., (9) W.Pine 6 N58W 24.07 ft.
 1972 survey by Theodore H. Weinert #19846 Fd. 1" Iron Pipe, same witnesses as Griffin, MC on the side of Lake of the Woods is N4-46-37W 3776.48 ft., SW 6 S1-58-44W 2629.62 ft.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found 1" x 36" long iron pipe extending 8" above the surface. A trailer home bears S39E 266 feet more or less. I set the iron 6" below the surface and placed a 2" x 30" iron pipe with brass cap directly over it. Witnesses 1 and 2 are gone. Witness 3 and 4 are stumps. Witnesses 5 through 8 are in good condition. Witness 9 is dead. I could find no conflicting information that would lead to another location. This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/4 corner common to section 1 of T20N R15W and section 6 of T20N R14W
 Monu. Set a 2" x 30" Iron Pipe with brass cap.
 Witnesses:
 60d in the northwest side of a R.Pine 24 N37E 27.68 ft. (5)
 60d in the northeast side of a R.Pine 24 N42W 36.65 ft. (6)
 60d in the northeast side of a R.Pine 13 S72E 30.84 ft. (7)
 60d in the northwest side of a R.Pine 7 S33W 40.62 ft. (8)
 Fiberglass Post S10W 0.75 ft.
 60d in the north side of a R.Oak 10 S88W 36.65 ft.

Peer Group Reviewed and Approved
 Date: 10-17-95
 Kenneth L. Ross
 Mason County Surveyor

SIGNED BY Patrick R. Leemon DATE October 15, 1995

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



LIBER **3** PAGE **319**

SURVEYOR'S MICHIGAN REGISTRATION NO. _____