

SURVEY & REMONUMENTATION

DEC 18 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --: LOCATED IN --: CORNER CODE NUMBER

1. PUBLIC LAND SURVEY _____ T. _____ 20N N. 15W E. M5 S., R. _____ W.

2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. S., R. _____ E. W.

3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.

4. LOT NO. _____, RECORDED PLAT _____

5. PRIVATE CLAIMS _____

FILED

AT 10:25 O'CLOCK *AM*

OCT 18 1995

MARY GOLDEN KOLASKI
MASON COUNTY
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on October 15, 1995, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Section corner common to sec's 12 & 13 of T20N R15W and sec's 7 & 18 of T20N R14W**
- 1838 survey by Mullett and Brookfield Set Wood Post, (1) Y.Pine 16 S15W 50 links, (2) Y.Pine 16 N50W 75 links
- 1905 survey by Robert O. Towns Fd. GLO stake and stumps of both BT's, S1/4 12 West 2699.4 ft.
- 1907 Survey by John Millard Fd. GLO stake and both BT's., (3) Y.Pine 6 S17W no dist. NE 12 North 5280 ft.+-
- 1915 survey by George H. Johnson #504 No monument given, (4) W.Oak 9 S41E 10.5 ft., (5) Y.Pine 9 S21W 11.5 ft., (over)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the 5" square by 60" long concrete monument w/ brass cap by Griffin, extending 18" above the surface and in good condition, 150 feet west of the centerline of FR 5203 and on the north aspect, 42 feet north of the top of a ridge. This corner is 2000 feet south of the intersection of FR 5331 and FR 5203. Witnesses 1, 2, 3, 6 and 7 are gone. Witnesses 4, 5, 8, 9 and 10 are in good condition. I could find no conflicting information that would lead to another location. This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Section corner common to sec's 12 & 13 of T20N R15W and sec's 7 & 18 of T20N R14W Monu.** The 5" square by 60" long concrete monu. with 3" brass disk was left in place.
- Witnesses:
- 10" spike in the south side of a R.Pine 11 N73W 7.52 ft. (9)
- 10" spike in the northwest side of a W.Pine 6 N70E 13.43 ft. (8)
- 60d nail in the southwest side of a W.Oak 14 S39E 10.86 ft. (4)
- 60d nail in the west side of a R.Pine 16 S21W 11.26 ft. (5)
- P.Post 4 North 2.09 ft. (10)
- 60d nail in the southwest side of a W.Pine 8 N36W 39.70 ft.

Peer Group Reviewed and Approved
Date: _____
Kenneth L. Ross
Mason County Surveyor

SIGNED BY Patrick R. Leemon DATE October 15, 1995

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



LIBER 3 PAGE 321

SURVEYOR'S MICHIGAN REGISTRATION NO. _____