

MAR 16 1998


LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION
MASON
 (County)

Located in: Corner Code #

1. Public Land Survey	T 20N R 15W	M-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____



Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kenneth L. Ross, in a field survey on September 12, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-8 East 1/4 Corner for Section 24, T20N, R15W, on the Township Line,

1838, Mullett & Brookfield, GLO, boundary survey
 Set Wood Post
 #1 White Oak 10" N 38° W 81ks. (5.28')
 #2 White Pine 8" S 42° W 291ks. (19.14')

1981, Robert A. Griffin, RLS #13584
 Set 5" sq. x 36" long conc. monument w/ brass cap
 #3 White Oak 8" N 84° W 54.44'
 #4 White Pine 25" S 23° E 119.45'
 #5 White Oak 8" S 31° W 69.64'
 #6 Pine Post North 1.57'
 Recovered this corner by proportional measurement and on a straight line between controlling corners as of L. 02, P. 437, Lake Co. Register of Deeds

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 East 1/4 Corner for Section 24, T20N, R15W, on the Township Line,

On September 12, 1997, I Ken Ross and Kevin Pritchard (survey tech.) found a 5" square conc. monument with a 3" brass cap, to identify this monument as the 1/4 corner. This corner sets 20 feet west of the center-line of Tyndall Road, one foot below the surface of the ground. I found no evidence to dispute this location for the corner.


Condition of recorded witnesses are; #1 Gone #2 Gone #3 Found in good condition #4 Found dead
 #5 Found in good condition #6 Found in good condition

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 East 1/4 Corner for Section 24, T20N, R15W, on the Township Line,

I accepted Robert Griffin's 5" sq. concrete monument as substantial marker for this corner and established it as a careful and faithful re-establishment of the position of the original corner.

(ext. BT #3) White Oak 12" N 84° W 54.44' (10" dock spike in North side of tree)
 (ext. BT #5) White Oak 13" S 31° W 69.64' (10" dock spike in NE side of tree)
 (new BT) Black Oak 18" N 81° W 10.65' (60 d spike in North side of tree)
 (ext. BT #6) Pine Post 4" x 4' North 1.57' 16 p. nail in south side of post



Signed by Kenneth L. Ross Date October 1, 1997
 Surveyor's Michigan License No. 17634

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1976
 REVISED JAN. 1983
 ADAPTED FOR WORD PROCESSING MARCH 1985

LIBER 4 PAGE 113

Peer Group Reviewed and Approved
 Date: Oct 2, 1997
Kenneth L. Ross
 Mason County Surveyor