

MAR 16 1998

LAND CORNER RECORDATION CERTIFICATE

SECTION

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 20N N. S., R. 15W E. W.	G2
2. PROPERTY CONTROLLING IN SECTION	T. N. S., R. E. W.	<i>Seg. 2</i>
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

FILED

AT 10:10 O'CLOCK *a*

NOV 17 1994

MARY GOLDEN KOLASKI
MASON COUNTY
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Patrick R. Leemon do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram -- over) were, in a field survey on October 30 1994, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

1/4 corner common to sections 3 and 4 of T20N R15W

<p>1839 survey by John Brink Set Wood Post #1 P.Pine 6 N4E 812 links no other witnesses available.</p>	<p>1918 survey by C.E. Mitchell Co. Sur. Set Concrete Monument #2 Oak 10 N32W 96 links #3 Oak 9 S82W 100 links</p>	<p>1970 survey by Robert A. Griffin #13584 Searched for and found the Mitchell monument. Replaced it w/ a 5" sq. by 36" long conc. monument w/ brass cap. #4 P.Post 4 West 33 feet #5 R.Pine 7 N57E 59.46 feet #6 R.Pine 4 S70W 54.07 feet #7 R.Pine 4 N53W 63.68 feet</p>
--	--	--

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I found the 5" square by 36" long concrete monument w/ brass cap by Griffin buried 5" beneath the surface and 4 feet East of the centerline of the N-S road. Witnesses 1 through 3 are gone. Witnesses 4 through 7 are in good condition. Liber 1 Page 40 by Griffin documents the history of this corner. I could find no conflicting information that would lead to another location. This monument is accepted as the best available evidence of the position of the original corner.

Peer Group Reviewed and Approved
Date: Feb 22 1995
Kenneth L. Ross
Mason County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/4 corner common to sections 3 and 4 of T20N R15W

Monu. The 5" square by 36" long concrete monu. with 3" brass disk was left in place

Witnesses:

- B.Oak 11 S56E 96.36 feet
- P.Post 4 West 32.88 feet (#4)
- R.Pine 13 N57E 59.52 feet (#5)
- R.Pine 8 S70W 53.97 feet (#6)
- R.Pine 8 N53W 63.73 feet (#7)

STATE OF MICHIGAN

PATRICK R. LEEMON

LAND SURVEYOR

NO. 31595

LICENSED LAND SURVEYOR

Peer Group Reviewed and Approved
Date: Feb 22 1995
Kenneth L. Ross
Mason County Surveyor

SIGNED BY Patrick R. Leemon DATE October 30, 1994
 SURVEYOR'S MICHIGAN REGISTRATION NO. 31595 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____
 APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)