

**SURVEY & REMONUMENTATION**

**MAR 16 1998**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION  
For corners in Mason  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- 1. Public Land Survey T 20N R 16W \_\_\_\_\_ C-13  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

FILED

AT 4:04 O'CLOCK P

**NOV 20 1997**

**MARY GOLDEN KOLASKI**  
**MASON COUNTY**  
**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Richard L. Hays, in a field survey on August 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

C-13 SOUTHEAST CORNER OF SECTION 31, T20N-R16W

1839: G.L.O Survey 1983: Lawrance Slater Survey #7439  
 12" Beech N-64°-E 47 lks (1) L.C.R.C. LIBER 2, Pg 175  
 8" Beech N-35°-W 31 lks (2) Found 1/2" Re-Rod  
 Top of Telephone Riser N-45°-E 54.00' (4)  
 Stop Sign Post S-50°-E 63.45' (5)  
 Deputy County Surveyor Power Pole S-05°-W 29.06' (6)  
 No Witnesses Face Stop Sign Post S-20°-W 27.45' (7)

1981: Ross Survey R.L.S. #17634  
 SW Corner to South Quarter Corner Section 32 2622.30' (3)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

C-13 SOUTHEAST CORNER OF SECTION 31, T20N-R16W  
 August 1997: Found 1/2" Re-Rod. Condition of the Witnesses are as follows:

12" Beech	N-64°-E	47 lks (1)	(GONE)
8" Beech	N-35°-W	31 lks (2)	(GONE)
SW Corner to South Quarter Corner Section 32		2622.30' (3)	(FOUND)
Top of Telephone Riser	N-45°-E	54.00' (4)	(GONE)
Stop Sign Post	S-50°-E	63.45' (5)	(FOUND)
Power Pole	S-05°-W	29.06' (6)	(GONE)
Face Stop Sign Post	S-20°-W	27.45' (7)	(GONE)

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C-13 SOUTHEAST CORNER OF SECTION 31, T20N-R16W  
 August 1997: Replace the 1/2" Re-Rod with the Standard Mason County Monument as a careful and faithful re-establishment of the position of the Original Corner.

1/2" Re-Rod	N-10°-W	60.23'
1/2" Re-Rod	N-18°-E	63.65'
1/2" Re-Rod	S-80°-W	29.10'
Spike in NE Side of Power Pole	S-04°-E	56.50'
South Edge of Stop Sign 1/2" Re-Rod	S-14°-W	44.45'
5/8" Re-Rod	East	29.04'

Signed by Richard Hays Date 10/6/97

Surveyor's Michigan License No. 25847

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 21, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 ADAPTED FOR WORD PROCESSING MARCH, 1993

LIBER 4 PAGE 185 Date Nov 21 1997