

**FEB 08 2000**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in MASON Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 20N R 16W I-6  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**FILED**

AT 1:30 O'CLOCK P M

**JUL 22 1999**

**MARGARET KOLASKI ELLIOTT**  
**MASON COUNTY**  
**REGISTER OF DEEDS**  
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kenneth L. Ross, in a field survey on May 22, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 1/4 Corner Common to Sections 14 and 15, T.20N., R.16W.,

- |  |  |  |
|--|--|--|
| G.L.O. John Brink<br>1839<br>Set quarter section post<br>(1) Beech, 13", S80°W, 46 links(30.36')<br>(2) Beech, 10", N08°E, 12 links(7.92')   | January, 1979, LCRC, Liber 2, page 70<br>Norman L. Ochs, "fd. 5" sq. Monument"<br>Witnesses (3) thru (5) given<br>(7) 4- 3" twin Locust, S77°E, 27.03' | June, 1996, Act 132<br>K.L. Ross, "fd USFS Mon."<br>No Witnesses, No Distances                                 |
| Sept. 1908, Book 2, page 208 & 209<br>R.O. Towns, "Planted Pipe"<br>Distance North to I-5, 2650.56'<br>Distance South to I-7, 2650.56'   | December, 1984, Act 132<br>K.L. Ross, "fd USFS Monument"<br>No Witnesses Given<br>Distance North to I-5, 2643.55'<br>Distance South to I-7, 2650.03'   | November, 1998, Act 132<br>K.L. Ross, "fd USFS Mon."<br>No Witnesses Given.<br>Distance North to I-5, 2643.24' |
| April, 1966, LCRC, Liber 1, page 105<br>Robert A. Griffin, "Fd. 1 1/2" pipe X 26"<br>Replaced with 5"sq. X 36" Conc. Monument<br>(3) SW Corner Conc. Basement N64°E, 316.30'<br>(4) Center of a locust, 8", S30°E, 58.55'<br>(5) 16d spike NW side P.P. S09°W, 196.05'<br>(6) 6"X7' Cedar Post, West, 33.00' | October, 1988, Act 132<br>K.L. Ross, No Comment on Cor.<br>Distance South to I-7, 2650.03'   |  |


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1/4 Corner Common to Sections 14 and 15, T.20N., R.16W.,

Found USFS Monument as described above by Griffin. 1 1/2" pipe on South Side of Monument. Witnesses (1), (2) and (6) have been destroyed. Witnesses (3), (4) and (5) are standing and in good condition. I found no other evidence to dispute the location of this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 1/4 Corner Common to Sections 14 and 15, T.20N., R.16W.,

- I left the USFS Monument in place 1.0' below the top of the gravel surface. This corner ~~is~~ <sup>is the best</sup> available evidence of the re-establishment of the Original Corner.
- (3) SW Corner of Concrete Basement N64°E, 316.30'
  - (4) Locust, 28", set 60d spike, SW side, S26°E, 58.42'
  - (5) existing 16D spike NW side of P.P. S09°W, 196.05'
  - (8) NBT White Pine, 6", set 60d spike NE side, N61°W, 42.76'

**LIBER 4 PAGE 278**



Signed by [Signature]  
 Surveyor's Michigan License No. 17634

Date July 21

Peer Group Reviewed and Approved  
 Date: 7-14-99  
[Signature]  
 Kenneth L. Ross