

**FEB 08 2000**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in MASON (County)

Located In: Corner Code #

- 1. Public Land Survey T 20N R 16W J-5
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

FILED  
AT 1:28 O'CLOCK P. M  
JUL 27 1999  
MARGARET KOLASKI ELLIOTT  
MASON COUNTY  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kenneth L. Ross, in a field survey on May 22, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
J-5, 1/4 Corner Common to Sections 11 and 14, T.20N., R.16W.,  
GLO by John Brink, July, 1956, Dwg. K-17  
1839 K.B. Stephens, No Comment on Cor.  
"Set quarter section post" No Distances

September, 1908, Book 2, Page 208  
R.O. Towns, "Plow Colter"  
No Witnesses Given  
Distance West to I-5, 2636.04'  
Distance East to K-5, 2636.04'

January, 1979, LCRC, Liber 2 pg 71  
Norman L. Ochs, "set 2" pipe with  
1/4" rod inside halfway on line"  
(5) White Pine, 6", N11°W, 66.48'  
(6) White Pine, 4", N65°W, 29.58'  
(7) White Oak, 6", S11°W, 8.68'

July, 1920, C.E. Mitchell (Section)  
January, 1922, DeYoung (Replat)  
(same drawing) "Government Stake"  
(3) White Oak, 13", S63°30'E, 33.00'  
(4) Black Oak, 11", N60°E, 26.20'  
Distance West to I-5, 2608.00'  
Distance East to K-5, 2650.40'

December, 1984, Act 132, K.L. Ross  
"Fd 1/4" iron by RLS 22439"  
Witnesses (5), (6) & (7) Given  
Distance West to I-5, 2631.31'  
Distance East to K-5, 2631.81'  
January, 1988, Act 132  
K.L. Ross, No comment on cor.  
Distance South to C 1/4 cor, 2626.30'

May, 1988, Act 132, K.L. Ross  
"Existing Iron by Ochs" No Wit.  
Distance West to I-5, 2631.23'  
Distance East to K-5, 2631.41'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
J-5, 1/4 Corner Common to Sections 11 and 14, T.20N., R.16W.,

Found 1/4" rerod & cap #22439 (Ochs) inside a 2" pipe on west side of two track road running southeasterly and about 150 feet south of an East-West Two Track Road. Witnesses (1), (2), (3) and (4) have been destroyed. Witnesses (5), (6) and (7) are standing and in good condition. I could find no other evidence to dispute the location of this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
J-5, 1/4 Corner Common to Sections 11 and 14, T.20N., R.16W.,  
I replaced the 1/4" rerod and 2" pipe in the exact location with a Standard 3" Cast Iron Harrison Monument flush with the ground. This corner accepted as the best available evidence of the re-establishment of the position of the original corner.

- (5) White Pine, 9", existing 60d spike, east side, N11°W, 66.48'
- (6) White Pine, 7", existing 60d spike, NE side, N65°W, 29.58'
- (7) White Oak, 10", existing 60d spike, West side, S11°W, 8.68'
- (8) NET, White Pine, 8", set 60d spike, North side, S86°E, 32.05'
- (9) NET, Twin 8" White Oak, set 60d spike, West side, S58°E, 48.43'

Signed by [Signature] Date July 21, 1999  
Surveyor's Michigan License No. 17634

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1982  
ADAPTED FOR WORD PROCESSING MARCH, 1992

LIBER 4 PAGE 273



Peer Group Reviewed and Approved  
Date: 7-14-99  
[Signature]  
Kenneth L. Ross  
Mason County Surveyor