

DEC 29 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Mason (County) Located In: Corner Code #
1. Public Land Survey T 20N R 17W H-13
2. Property Controlling in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number
FILED
AT 2:58 O'CLOCK P M
NOV 24 1998
MARY GOLDEN KOLASKI
MASON COUNTY
REGISTER OF DEEDS

Grid table with columns A-M and rows 1-13 containing numbers 1-36.

I, Kenneth L. Ross, in a field survey on October 24, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GOVERNMENT SURVEY Mullett and Brookfield, 1838 to 1839
(1) Beech, 14", N52°E, 28 links, (18.48')
(2) Beech, 6", N64°W, 37 links (24.42')
Set Post
R.O. TOWNS, BOOK 2, PAGE 167-168
June, 1907, Stated located 1/4 Cor by stake and planted iron,
Distance East to I-13, 2634.72'
Distance West to G-1, 2641.32'
MASON COUNTY ROAD COMMISSION, 1961
Stone and Iron
(3) Rd. Name Sign, SE, 45.00'
(4) P.P. SW, 69.4'
(5) P.P. NW, 47.2'
(6) USFS Sign, NW, 52.5'

Kenneth B. Stephens, 1967 Tied this corner, no witnesses taken does not state what was found. Shows that the N 1/4 Corner of Section 2, (H-1) T.19N., R.17W, is East 7.23'.

LCRC Herbert Fluharty, RLS, Liber 1, Page 269, States Found Monument Box,
(7) Project Marker, N28°E, 74.23'
(4) P.P. S23°W, 69.8'
N1/4 Corner Section 3, T.19N., R.17W., East 7.30'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1" square boat spike 12" long as a riser to a 1 1/4" pipe in a monument box in the center-line of Townline Road. The boat spike was bent on top and measured 7.30 feet West of the N1/4 Corner of Section 3, T.19N., R.17W., (H-1) while the 1 1/4" pipe measured 7.23' west of the N 1/4 Corner of Section 3, T.19N., R.17W., (H-1)


Condition of record witnesses as follows: (1) gone, (2) gone (3) moved, (4) fair condition, ((5) gone (6) gone (7) good condition,

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1" square X 12" long boat spike with a 5/8" X 24" re-rod with a 3" aluminum cap stamped (Mason County Monument) inside the 1 1/4" pipe inside the monument box. This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

- Ex "B.T." (4) P.P. S 23°W, 69.92 feet (60d spike SE side)
Ex "B.T." (7) Project Marker N32°E, 74.23 feet
(8) P.P. N 21° W, 68.95 feet (60d spike NE side)
(9) Guy Pole, S 34° E, 49.98 feet (60d spike NW side)
(10) Corner H-1, T.19N., R.17W., East, 7.23 feet

Signed by [Signature] Date Nov 19, 1998
Surveyor's Michigan License No. 17634



Approved by Peer Review Group On 11-19-98
Kenneth L. Ross, County Representative [Signature]

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993