

DEC 9 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mason
 (County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 20N. R 17W. L-13
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____

Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

FILED
 AT 2:59 O'CLOCK P M
 NOV 21 1998
 MARY GOLDEN KOLASKI
 CLERK
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kenneth L. Ross, in a field survey on October 10, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13 S ¼ Corner Section 36, T.20N., R.17W.,

ORIGINAL GOVERNMENT SURVEY

Mullett and Brookfield, 1837 to 1838
 Set quarter sec. post

- (1) Elm, 8", N59°E, 36 links (23.76')
- (2) Elm, 7", N35°W, 29 links, (19.14')

Lawrence Slater, PLS, LCRC, Liber 2, page 191, August, 1983. Michigan Dept. of Transportation States Found 10"X 14"X 20" tapered Red Stone, buried 28". Raised with a 23"X 1" Steel Rod buried 4" below the road surface.
 S 87° 44' 40.77"E, 5.28 feet to a ¾" steel rod.
 No other witnesses given.

No other research on this corner was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 S ¼ Corner Section 36, T.20N., R.17W.,

On October 10, 1998, I found a 1"X 23" Iron as a riser to a stone that is 30 " below the road surface.

Condition of Record Witnesses are as follows: (1) Gone, (2) Gone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 S ¼ Corner Section 36, T.20N., R.17W.,


I removed the 1" X 23" iron pin and place a 4" X 20" Harrison Cast Iron Monument stamped "MASON COUNTY MONUMENT" on top of the stone in the exact location of the 1" X 23" iron pin. This corner is accepted as a careful and faithful re-establishment of the original corner.

- (3) P.P. N 80°E, 112.19', (60d spike NW side)
 - (4) P.P. N 05°E, 54.64', (60d spike East Side)
 - (5) Guard Rail Post N 24° W, 19.71', (60d spike on top)
 - (6) Guard Rail Post, S 35°W, 18.20', (60d Spike on top)
 - (7) Guard Rail Post, S 75°W, 48.85', (60d spike on top)
- L-1, T.19N., R.17W., East 5.20 feet.

Signed by Kenneth L. Ross

Date 11-19-98

Surveyor's Michigan License No. 17634



Approved by Peer Review Group On 11-19-98
 Kenneth L. Ross, County Representative [Signature]