

SURVEY & REMONUMENTATION

JUL 06 1998

MECOSTA COUNTY REMONUMENTATION PROGRAM

CORNER APPROVED BY PEER GROUP ON APRIL 17, 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER'S OFFICE }
Mecosta County, } ss.

For corners in MECOSTA (County) Located in: _____ Corner Code # _____

1. Public Land Survey	T 13N R 09W	D-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4 Lot No. _____ Recorded Plat _____

5. Private Claims _____

Received for Record, the 29 day of June A.D., 1998 at 3:15 o'clock P.M., and Recorded in Liber _____ of _____ on Page _____

Joanne [Signature]
Register of Deeds
Mecosta County

Register of Deeds Stamp & File Number

I, JAMES G. KNAPP, in a field survey on MARCH 27, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, ABNER E. VAN NESS, SET POST IN MARCH 1838, CORNER POST PLACED 39.19 CHAINS (2586.54 FEET) FROM N.E. AND N.W. CORNER, SECTION 32, AND WITNESSED: BASSWOOD 6" S37°W 63 LINKS (41.58 FEET)
R. OAK 20" N37°E 14 LINKS (9.24 FEET)

NOTES AT MECOSTA COUNTY ROAD COMMISSION, DATED AUG. 1928, NOTES CORNER AS, BEING 53+57 FROM SOUTH 1/4, SECTION 32, AND WITNESSED: F.P. CONCRETE N.E. 46.3'
F.P. CONCRETE N.W. 47.1'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" X 24" IRON PIPE, BURIED 6" BELOW GRAVEL ROAD SURFACE, 5' WEST OF CENTER OF 165TH. AVENUE (24' GRAVEL NORTH - SOUTH), AND IN LINE WITH CENTER OF 1 MILE ROAD (20' GRAVEL EAST - WEST).

APPROVED BY MECOSTA CO. PEER GROUP IN ACCORDANCE WITH P.A. 345 of 1990

James G. Knapp
CHAIRMAN
DATE APRIL 17, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11, 1/4 CORNER COMMON TO SECTIONS 29 AND 32, T13N-R09W.
FOUND 1" X 24" IRON PIPE, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
REMOVED THE 1" IRON PIPE, AND PLACED IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, WITH THE IRON PIPE INSIDE, BURIED 8" BELOW ROAD SURFACE, AND WITNESSED:
S.W. CORNER OF 30" X 36" XN4' HIGH (12" SQUARE TOP) CONCRETE POST AZ. 45°, 46.4 FEET
FOUND SPIKE IN N.W. SIDE OF 20" WALNUT AZ. 64°, 63.81 FEET
SET 40d SPIKE IN S.W. SIDE OF UTILITY POLE AZ. 155°, 147.20 FEET
S.E. CORNER OF 30" X 36" X 4' HIGH (12" SQUARE TOP) CONCRETE POST AZ. 315°, 47.1 FEET
SET 40d SPIKE IN S.W. SIDE OF UTILITY POLE AZ. 333°, 49.14 FEET



Signed by *James G. Knapp*
Surveyor's Michigan License No. 25853

Date APRIL 14, 1998