

OCT 25 1999

MECOSTA COUNTY REMONUMENTATION PROGRAM

CORNER APPROVED BY PEER GROUP ON FEBRUARY 12, 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF MECOSTA RECEIVED FOR RECORD

For corners in

MECOSTA

(County)

Located In:

Corner Code #

'99 JUL -2 P2:59

Joanna Brown REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 13N R 09W F-05
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4 Lot No. Recorded Plat
5. Private Claims

I, JAMES G. KNAPP, in a field survey on AUGUST 27, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, ABNER E. VAN NESS, SET POST IN SECOND QUARTER OF 1838, CORNER POST PLACED 39.93 CHAINS (2635.38 FEET) FROM CORNER COMMON TO SECTIONS 9, 10, 15 AND 16, AND WITNESSED: BEECH 10" N21°W 09 LINKS (5.94 FEET) BEECH 6" N88°W 15 LINKS (9.90 FEET)

CORNER CALLED FOR IN COUNTY SURVEYOR'S BOOK NO. 1, PAGE 105, (FROM FIELD BOOK NO. 4, PAGE 46), BY L. W. JUNE, COUNTY SURVEYOR, DATED APRIL 8 -9, 1902, AND NOTED AS, "OLD IRON PIN", AND BEING 82.00 CHAINS (5412.00 FEET) FROM NORTH 1/4 CORNER, SECTION 9.

Grid table with columns A-M and rows 1-13. Cell (6,9) contains a black dot.

APPROVED BY MECOSTA CO. PEER GROUP IN ACCORDANCE WITH P.A. 945 of 1990

James G. Knapp CHAIRMAN DATE FEB. 12, 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 16" RE-BAR, BURIED 3" BELOW GRAVEL ROAD SURFACE, AT 18" DEEP FOUND ENGINE CONNECTING ROD, (2) 1/2" X 4" BOLTS IN NEST OF STONES, AT 28" DEEP FOUND REMAINS OF WOOD STAKE AND A PIECE OF TIN. CORNER IS CENTER OF 4 MILE ROAD (24' GRAVEL EAST - WEST), AND CENTER OF 155th AVENUE (22' BITUMINOUS - NORTH AND 24' GRAVEL - SOUTH).

SET HIGHWAY MONUMENT BOX DURING BITUMINOUS PAVING OF 155th AVENUE - NORTH IN SEPT. 1998.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-05, 1/4 CORNER COMMON TO SECTIONS 9 AND 16, T13N-R09W. FOUND 1/2" X 16" RE-BAR, BURIED 3" BELOW ROAD SURFACE, AT 18" DEEP FOUND ENGINE CONNECTING ROD, (2) 1/2" X 4" BOLTS IN NEST OF STONES, AT 28" DEEP FOUND REMAINS OF WOOD STAKE AND A PIECE OF TIN, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER. REMOVED THE 1/2" X 16" RE-BAR, CONNECTING ROD, (2) 1/2" X 4" BOLTS IN NEST OF STONES, AND PLACED IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, INSIDE OF A HIGHWAY MONUMENT BOX, AND WITNESSED: FOUND NAIL IN S.E. SIDE OF CORNER FENCE POST AZ. 38°, 77.96 FEET FOUND NAIL IN S.W. SIDE OF 10" APPLE AZ. 126°, 50.78 FEET STOP SIGN AZ. 238°, 44.35 FEET FOUND NAIL IN S.W. SIDE OF UTILITY POLE AZ. 316°, 59.88 FEET



Signed by James G. Knapp Surveyor's Michigan License No. 25853

Date, JUNE 2, 1999