

**SURVEY &
REMONUMENTATION**

MECOSTA COUNTY REMONUMENTATION PROGRAM

APR 04 1996

CORNER APPROVED BY PEER GROUP ON DEC. 7, 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

For corners in

Mecosta
(County)

Located In:

Corner Code #

95 DEC 19 P1 52

- | | | |
|------------------------------------|----------------------------------|------------|
| 1. Public Land Survey | Sec. 22 T <u>13N</u> R <u>9W</u> | <u>G-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

James Brown
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James J. Keller, in a field survey on Jan. 20 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- March 26, 1838, Abner E. Van Ness "Set Post Corner to Sections 15, 16, 21 & 22" 24" Cedar West
- Oct. 25, 1972, R. Benkert #1237
Tag E. Side 12" Poplar N14°W 42.0'
Tag N.E. Side 15" Oak S52-1/2°E 55.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Jan. 20, 1992, James J. Keller #10693 "Found 1/2" Rebar 18" long"
Set Nail N.E. Sd. 16" Maple N66°W 55.54'
Found Cap #30104 N04°E 33.00'
Found Nail N. Sd. 20" Ash S46°E 55.35'
Found Nail West Sd. 18" Ash S17°E 25.57'

APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 345 of 1990
James J. Knapp
CHAIRMAN
DATE DEC. 7, 1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Monument and is accepted as careful perpetuation of the location of the Original Monument.

- Found Nail and Set Tag N.E. Sd. 16" Maple N66°W 55.54'
Found Cap #30104 N04°E 33.00'
Found Nail and Set Tag N. Sd. 20" Ash S46°E 55.35'
Found Nail and Set Tag West Sd. 18" Ash S17°E 25.57'

Signed by James J. Keller Date Nov 30, 1995
Surveyor's Michigan License No. #10693

