

**SURVEY &  
REMONUMENTATION**

**MECOSTA COUNTY REMONUMENTATION PROGRAM**

APR 04 1996

CORNER APPROVED BY PEER GROUP ON DEC. 7, 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF MECOSTA  
RECEIVED FOR RECORD

For corners in  
MECOSTA  
(County)

Located In:

Corner Code #

95 DEC 19 P1:52

1. Public Land Survey	Sec 22	T 13N	R 9W	H-7
		T	R	
		T	R	
		T	R	
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

*Jessie Brown*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, James J. Keller, in a field survey on Jan 20 1992, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

March 26, 1838, Abner E. Van Ness "Set 1/4 Sec. Post"  
8" Cedar N38°E 08 Links  
8" Birch S38°W 16 Links

April 12-14, 1902 Lyman W. June, County Surveyor, "Iron Pipe"

Oct. 25, 1972, R. Benkert #1237 Liber 10, Pages 100 & 101  
Tag N.E. sd 8" Poplar S44-1/2°E 54.4'  
Tag S.E. sd Corner Fence Post S32-1/2°W 37.55' (Not Found)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Jan. 20, 1992, James J. Keller #10693 Found 1/2" Rebar 1' North of Centerline Gravel Road  
Found Nail N.E. sd. 15" Popple N15°W 28.98  
Found Nail S.E. sd. 28" White Oak N50°E 45.83'  
Telephone Box #14499 S51°E 47.24'  
Found Nail N.W. sd. Power Pole S53°W 47.11'  
Found Nail & Tag #1237 14" Popple S39°E 52.38'  
No other Irons Found

APPROVED BY MECOSTA CO. PEER GROUP  
IN ACCORDANCE WITH P.A. 345 of 1990

*James M. Knapp*  
CHAIRMAN  
DATE DEC. 7, 1995


**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set Remonumentation Monument and is accepted as careful perpetuation of the location of the Original Monument.

Set 60d and Set tag N.E. sd. 15" Popple N15°W 28.98  
Set 60d and Set tag S.E. sd. 28" White Oak N50°E 45.83'  
Found Nail & Tag #1237 and Set 60d and Set tag 14" Popple S39°E 52.38'  
Set 60d and Set tag N.W. sd. Power Pole S53°W 47.11'  
Set 60d and Set tag N.E. sd. 10" Ash S60°E 64.49'

Signed by James J. Keller Date Nov. 30, 1995

Surveyor's Michigan License No. #10693



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1976  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1989