

REMONUMENTATION

# MECOSTA COUNTY REMONUMENTATION PROGRAM

NOV 18 1997

CORNER APPROVED BY PEER GROUP ON OCTOBER 10, 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Mecosta  
(County)

Located In:

Corner Code #

- |                                    |   |     |   |     |      |
|------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey              | T | 13N | R | 09W | K-01 |
|                                    | T |     | R |     |      |
|                                    | T |     | R |     |      |
|                                    | T |     | R |     |      |
| 2. Property Controlling in Section | S | T   | R |     |      |
|                                    | S | T   | R |     |      |
| 3. Miscellaneous Property in Sec.  | S | T   | R |     |      |
|                                    | S | T   | R |     |      |
- 4 Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF MECOSTA  
RECEIVED FOR RECORD

'97 NOV -7 P2:23

*James G. Knapp*  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

I, JAMES G. KNAPP, in a field survey on SEPTEMBER 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Only one corner may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**  
DEPUTY SURVEYOR, ABNER E. VAN NESS, SET POST IN 1837. CORNER POST PLACED 39.63 CHAINS (2615.58 FEET) FROM 1/4 CORNER COMMON TO SECTIONS 1, AND 2, AND INTERSECTIONING NORTH BOUNDARY LINE 1.50 CHAINS (99.00) FEET EAST OF POST COMMON TO SECTIONS 35, AND 36 T14N-R09W, AND WITNESSED: BEECH 10" S77 1/2°W 10 LINKS (6.60 FEET)  
BEECH 6" S79°E 08 LINKS (5.28 FEET)

- NOTES AT MECOSTA COUNTY ROAD COMMISSION SHOW,
- (1) FROM L. W. JUNE, NOTES DATED JUNE 27 - 30, 1897, NOTES CORNER AS BEING 25.50 CHAINS (1683.0 FEET) FROM WEST 1/4, AND 39.28 CHAINS (2592.48 FEET) FROM NORTH 1/4 CORNER, SECTION 1, T13N-R09W, WITH CORNER NOTED AS, "OLD COR. P. STP. 20, S23 1/2°E 15 LINKS",
  - (2) FROM W. WILLITS, NOTES CORNER AS, "IRON", AND WITNESSED: WILLOW 14" N40°W 44'  
POPLAR 6" S23°W 60.5'
  - (3) FROM E. E. SOURS, DATED NOV. 1, 1918, NOTES DISTANCE OF 1296 FEET TO N.E. CORNER OF N.W. 1/4 - N.W. 1/4, AND 1258 FEET TO S.W. CORNER OF N. 1/2 - S.W. 1/4 - N.W. 1/4, FROM N.W. CORNER OF SECTION 1.

APPROVED BY MECOSTA CO. PEER GROUP  
IN ACCORDANCE WITH P.A. 345 of 1990  
*James G. Knapp*  
CHAIRMAN  
DATE OCT. 10, 1997

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
FOUND, 2" WELL POINT IN LAWN AREA.

MEASURED DISTANCE TO THE NORTH 1/4 CORNER IS 2588.82 FEET, AND TO THE WEST 1/4 CORNER IS 1629.15 FEET OF SECTION 1.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
K-01 - CORNER COMMON TO SECTIONS 1 AND 2, T13N-R09W.

FOUND, 2" WELL POINT, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER- PLACED A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, (OVER THE 2" WELL POINT), AND WITNESSED:  
SET 60d SPIKE W/REMONUMENTATION TAG IN S.E. SIDE OF 24" BOX ELDER AZ. 49°, 34.87 FEET  
SET 60d SPIKE W/REMONUMENTATION TAG IN NORTH SIDE OF UTILITY POLE AZ. 142°, 83.41 FEET  
CORNER COMMON TO SECTIONS 35 AND 36, T14N-R09W (COUNTY REMONUMENTATION MONUMENT) AZ. 268°, 99.14 FEET  
S.W. CORNER OF HOUSE AZ. 341°, 96.78 FEET

Signed by James G. Knapp Date OCTOBER 9, 1997  
Surveyor's Michigan License No. 25853

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 25, 1983  
REVISED MAY 1984  
ADAPTED FOR PROCESSING MARCH 1988

