

REMONUMENTATION MECOSTA COUNTY REMONUMENTATION PROGRAM

CORNER APPROVED BY PEER GROUP ON OCTOBER 10, 1997

NOV 18 1997

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
MECOSTA  
 (County)

Located In: Corner Code #

1. Public Land Survey T 13N R 09W K-02  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R

3. Miscellaneous S T R  
 Property in Sec. S T R

4 Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 COUNTY OF MECOSTA  
 RECEIVED FOR RECORD

'97 NOV -7 P2:23

*Joanne Brown*  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on SEPTEMBER 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, ABNER E. VAN NESS, SET POST IN 1837. CORNER POST PLACED 40.00 CHAINS (2640.00 FEET) FROM CORNER COMMON TO SECTIONS 1, 2, 11, AND 12, AND WITNESSED: BEECH 12" N756°W 29 LINKS (19.14 FEET)  
 BEECH 6" S57 1/2°W 22 LINKS (14.52 FEET)

NOTES AT MECOSTA COUNTY ROAD COMMISSION, FROM L. W. JJNE, NOTES DATED JUNE 27 - 30, 1897, NOTES CORNER AS, "ORIGINAL P.S 24" S59 1/2°E 22 LINKS", AND BEING 25.50 CHAINS (1683.0 FEET) FROM N.W. CORNER AND 41.78 CHAINS (2757.48 FEET) FROM S.W. CORNER OF SECTION 1,

APPROVED BY MECOSTA CO. PEER GROUP  
 IN ACCORDANCE WITH P.A. 345 OF 1990

*James G. Knapp*  
 CHAIRMAN  
 DATE OCT. 10, 1997

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND, 2" WELL POINT IN BURIED 1" BURIED BELOW GRAVEL ROAD SURFACE, AND 4' EAST OF CENTER OF 130<sup>TH</sup>. AVENUE (24' GRAVEL), AND IN LINE WITH FENCE ROW - WEST AND 6' NORTH OF FENCE ROW - EAST, AFTER BITUMINOUS PAVING ON JUNE 15, 1994, CORNER IS 3.3' EAST OF CENTERLINE OF 130<sup>TH</sup>. AVENUE (22' BITUMINOUS).

MEASURED DISTANCE TO THE N.W. CORNER IS 1629.15 FEET AND TO S.W. CORNER IS 2749.88 FEET OF SECTION 1,

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-02 - 1/4 CORNER COMMON TO SECTIONS 1 AND 2, T13N-R09W.  
 FOUND, 2" WELL POINT, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER- PLACED A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, AND A HIGHWAY MONUMENT BOX, WHILE BITUMINOUS PAVING OF 130<sup>TH</sup>. AVENUE ON JUNE 15, 1994.

SET 60d SPIKE W/REMONUMENTATION TAG IN NORTH SIDE OF UTILITY POLE AZ. 101°, 63.39 FEET  
 SET 60d SPIKE W/REMONUMENTATION TAG IN SOUTH SIDE OF 10" TRIPLE CHERRY AZ. 272°, 108.19 FEET  
 SOUTH END OF 12" X 30' C.S.P. DRIVE CULVERT AZ. 226°, 46.3 FEET  
 SOUTH END OF 12" X 30' C.S.P. DRIVE CULVERT AZ. 308°, 40.2 FEET

Signed by James G. Knapp Date OCTOBER 9, 1997  
 Surveyor's Michigan License No. 25853

STATE OF MICHIGAN  
 JAMES G. KNAPP  
 CHAIRMAN  
 REGISTER OF DEEDS  
 FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1974  
 REDESIGNED JAN. 1984  
 ADAPTED FOR PROCESSING MARCH 1984