

MECOSTA COUNTY REMONUMENTATION PROGRAM
CORNER APPROVED BY PEER GROUP ON APRIL 17, 1998

SECTION _____

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF MECOSTA
 RECEIVED FOR RECORD

For corners in
MECOSTA
 (County)

Located In: _____

Corner Code # _____

'98 AUG 19 A9:53

- | | | | | | |
|------------------------------------|---|-------|---|-------|-------|
| 1. Public Land Survey | T | 13N | R | 09W | K-09 |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | T | R | _____ | _____ |
| | S | T | R | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | T | R | _____ | _____ |
| | S | T | R | _____ | _____ |

Joanna Brown
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4 Lot No. _____ Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on JULY 23, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, ABNER E. VAN NESS, SET POST IN MARCH 1838, CORNER POST PLACED 40.00 CHAINS (2640.00 FEET) FROM 1/4 CORNER COMMON TO SECTIONS 25 AND 26, AND BEING 24.50 CHAINS (1617.00 FEET) FROM LEFT BANK OF STREAM, AND NOTED TAMARACK 18" FOR CORNER POST.

ON NOV. 2-6, 1908, GEO. H. WILLITS, COUNTY SURVEYOR, NOTES IN COUNTY SURVEYORS RECORD BOOK No.1, PAGE 140, (FROM FIELD BOOK NO. 9, PAGE 7), NOTES CORNER AS, "STAKE", AND SHOWS A DISTANCE OF 2715.2 FEET TO EAST 1/4 CORNER, SECTION 23.

APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 145 of 1990

James G. Knapp
 CHAIRMAN
 DATE APRIL 17, 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/4" x 14" IRON PIPE SQUARE IRON WITH KNOB ON TOP, BURIED 15" BELOW GRAVEL ROAD SURFACE, 3' WEST OF CENTER OF 130TH. AVENUE (24' GRAVEL), AND IN LINE WITH FENCE AND TREE ROW - WEST, AND 10' SOUTH OF CEMETERY FENCE - EAST, AND BEING 1748' FROM SOUTH EDGE OF BRIDGE DECK OVER THE LITTLE MUSKEGON RIVER.

SET MONUMENT AND HIGHWAY MONUMENT BOX DURING BITUMINOUS PAVING ON JULY 23, 1997, CORNER IS 2.8' WEST OF CENTERLINE OF 130TH. AVENUE (20' BITUMINOUS).

MEASURED DISTANCE TO K-08 = 2715.20'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-09, CORNER COMMON TO SECTIONS 23, 24, 25 AND 26, T13N-R09W.
 FOUND 1" SQUARE IRON WITH KNOB ON TOP, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
 REMOVED THE 1" SQUARE IRON WITH KNOB ON TOP, AND PLACED IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, WITH THE 1" SQUARE IRON INSIDE, AND PLACED INSIDE OF A HIGHWAY MONUMENT BOX, AND WITNESSED:
 SET 60d SPIKE W/REMONUMENTATION TAG IN NORTH SIDE OF 2" JACK PINE
 N.W. CORNER OF 14" X 54" GRANITE HEADSTONE, "JOHNSON"
 SET 60d SPIKE W/REMONUMENTATION TAG IN WEST SIDE OF 30" MAPLE
 SET 60d SPIKE W/REMONUMENTATION TAG IN NORTH SIDE OF 26" WALNUT

- | | | |
|-----|------|-------------|
| AZ. | 70° | 36.98 FEET |
| AZ. | 126° | 101.88 FEET |
| AZ. | 167° | 107.47 FEET |
| AZ. | 277° | 25.27 FEET |



Signed by *James G. Knapp*
 Surveyor's Michigan License No. 25853

Date AUGUST 10, 1998