

MECOSTA COUNTY REMONUMENTATION PROGRAM

CORNER APPROVED BY PEER GROUP ON NOVEMBER 14, 1997 STATE OF MICHIGAN
 COUNTY OF MECOSTA
 RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'97 DEC 22 A8:43

For corners in
MECOSTA
 (County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 13N R 07W C-01
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4 Lot No. _____, Recorded Plat _____

5. Private Claims _____

James Brown
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on JUNE 27, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST IN 2nd QUARTER 1839. CORNER POST PLACED 40.64 CHAINS (2682.24 FEET) FROM 1/4 CORNER COMMON TO SECTIONS 5, AND 6, AND BEING 25 LINKS (16.50 FEET) WEST OF CORNER OF SECTIONS 31 AND 32, T14N-R07W, AND WITNESSED: ELM 14" S33°W 7 LINKS (4.62 FEET)
 ELM 10" S35°E 16 LINKS (10.56 FEET)

FIELD BOOK NO. 3, PAGES 152 - 155, AND COUNTY SURVEYOR RECORD BOOK NO. 1, PAGE 69, AT REGISTER OF DEEDS OFFICE SHOW NOTES BY L. W. JUNE, COUNTY SURVEYOR, ON JANUARY 23 THRU 26, 1900, WITH CORNER REPLACED BY ONE O.B.T. - DOWN, AND NOTED AS, "IRON ROD AND STONES", AND BEING 40.06 CHAINS (2643.96 FEET) FROM NORTH 1/4 CORNER AND 40.20 CHAINS (2653.20 FEET) FROM WEST 1/4 CORNER OF SECTION 5.

SURVEY & REMONUMENTATION

FEB 26 1998

SECTION

APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 345 of 1990

James G. Knapp
 CHAIRMAN
 DATE Nov. 14, 1997

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1' X 2' STONE, BURIED 15" BELOW ROAD SURFACE, WITH A 5/8" DIA. X 19" BOLT LYING HORIZONTALLY BELOW STONE AND 12' WEST OF CENTERLINE OF 50TH. AVENUE (21' BITUMINOUS), AND IN LINE WITH CENTER OF 6 MILE ROAD (18' GRAVEL) EAST AND WEST.

MEASURED DISTANCE TO D-01, T13N-R07W (AXE HEAD) IS 2641.78 FEET.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-01 - CORNER COMMON TO SECTIONS 5 AND 6, T13N-R07W.
 FOUND 1' X 2' STONE, BURIED 15" BELOW ROAD SURFACE, WITH A 5/8" DIA. X 19" BOLT LYING HORIZONTALLY BELOW STONE AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

LEFT STONE AND BOLT AS FOUND, CUT A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT TO 15" IN LENGTH AND PLACED OVER STONE, INSIDE OF A HIGHWAY MONUMENT BOX, AND WITNESSED:

- SET 60d SPIKE W/REMONUMENTATION TAG IN S.E. SIDE OF UTILITY POLE AZ. 52°, 65.31 FEET
- CORNER C-13, T14N-R07W (MECOSTA COUNTY REMONUMENTATION MONUMENT) AZ. 90°, 16.50 FEET
- SET 60d SPIKE W/REMONUMENTATION TAG IN S.W. SIDE OF UTILITY POLE AZ. 117°, 59.73 FEET
- SET 60d SPIKE W/REMONUMENTATION TAG IN N.W. SIDE OF 12" ASH AZ. 210°, 57.99 FEET
- SET 60d SPIKE W/REMONUMENTATION TAG IN N.E. SIDE OF 10" WHITE BIRCH AZ. 323°, 64.02 FEET

Signed by James G. Knapp Date OCTOBER 5, 1997
 Surveyor's Michigan License No. 25853

