

MECOSTA COUNTY REMONUMENTATION PROGRAM

CORNER APPROVED BY PEER GROUP ON NOVEMBER 14, 1997

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'97 DEC 22 A8:43

For corners in
MECOSTA
(County) Located In: Corner Code #

- | | | | | | |
|------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey | T | 13N | R | 07W | C-02 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

James Brown
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4 Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JAMES G. KNAPP, in a field survey on JUNE 27, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	•	5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST IN 2nd QUARTER 1839. CORNER POST PLACED 40.00 CHAINS (2640 FEET) FROM CORNER COMMON TO SECTIONS 29, 30, 31, AND 32, AND WITNESSED: BEECH 10" N80°E 8 LINKS (5.28 FEET)
BEECH 6" S50°W 15 LINKS (9.90 FEET)

FIELD BOOK NO. 3, PAGES 152 - 155, AND COUNTY SURVEYOR RECORD BOOK NO. 1, PAGE 69, AT REGISTER OF DEEDS OFFICE SHOW NOTES BY L. W. JUNE, COUNTY SURVEYOR, ON JANUARY 23 THRU 26, 1900, WITH CORNER NOTED AS, "SET STONE AT OLD COR. BY WITNESSES", AND BEING 39.82 CHAINS (2628.12 FEET) FROM S.W. CORNER AND 40.20 CHAINS (2653.20 FEET) FROM N.W. CORNER OF SECTION 5.

SURVEY & REMONUMENTATION

FEB 26 1998

SECTION

APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 345 of 1990

James G. Knapp
CHAIRMAN
DATE NOV. 14, 1997

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND PLOW POINT BURIED 15" BELOW ROAD SURFACE, WITH A 1' X 2' STONE ALONG THE N.W. SIDE OF PLOW POINT, AND 2.8' WEST OF CENTERLINE OF 50TH. AVENUE (21' BITUMINOUS), AND IN LINE WITH CENTER OF TYLER ROAD (18' GRAVEL) - WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-02 - 1/4 CORNER COMMON TO SECTIONS 5 AND 6, T13N-R07W.
FOUND PLOW POINT AND 1' X 2' STONE, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
REMOVED PLOW POINT AND SET A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT ALONG SIDE THE 1' X 2' STONE, INSIDE OF A HIGHWAY MONUMENT BOX, AND WITNESSED:
FOUND 8d NAIL IN S.E. SIDE OF UTILITY POLE AZ. 33°, 101.21 FEET
FOUND 8d NAIL IN WEST SIDE OF UTILITY POLE AZ. 168°, 209.48 FEET
FOUND 8d NAIL IN S.E. SIDE OF TREATED CORNER FENCE POST AZ. 224°, 46.97 FEET
FOUND 8d NAIL IN EAST SIDE 12" CHERRY (CLUMP OF 7) AZ. 346°, 98.47 FEET



Signed by *James G. Knapp*
Surveyor's Michigan License No. 25853

Date OCTOBER 5, 1997