

SURVEY & REMONUMENTATION
MECOSTA COUNTY REMONUMENTATION PROGRAM

MAR 03 1999

CORNER APPROVED BY PEER GROUP ON NOVEMBER 14, 1997

LAND CORNER RECORDATION CERTIFICATE

STATE OF MICHIGAN
 COUNTY OF MECOSTA
 RECEIVED FOR RECORD

Filing Requirement of Act 74, Mich. P.A. 1970

'98 DEC 28 A8:36

SECTION

For corners in MECOSTA (County)	Located In:	Corner Code #
1. Public Land Survey	T 13N R 07W	D-01
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Joseph Brown
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4 Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on JUNE 27, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 CORNER WAS NOT SET BY DEPUTY SURVEYOR'S.

FIELD BOOK NO. 3, PAGES 152 - 155, AND COUNTY SURVEYOR RECORD BOOK NO. 1, PAGE 69, AT REGISTER OF DEEDS OFFICE SHOW NOTES BY L. W. JUNE, COUNTY SURVEYOR, ON JANUARY 23 THRU 26, 1900, AND NOTED AS, "SINGLE AX", AND BEING 40.06 CHAINS (2643.96 FEET) FROM N.E. CORNER AND N.W. CORNER, SECTION 5.

CERTIFICATE OF SURVEY AS PER P. A. 132 OF 1970, BY JAN S. FOKENS, P.S. 21567, RECORDED ON OCT. 19, 1998, AND RECORDED IN LIBER 12, PAGES 439 THRU 442, AND NOTES CORNER AS, "FOUND AXE HEAD", AND SHOWS A DISTANCE OF 2641.77' TO N.W. CORNER AND 2636.56' TO N.E. CORNER, SECTION 5, AND WITNESSED:

- S20°W 30.10' SET NAIL AND TAG IN WEST FACE OF 13" MAPLE
- S80°W 68.15' SET NAIL AND TAG IN N.W. FACE OF 8" POPLAR
- S60°W 38.95' SET NAIL AND TAG IN N.W. FACE OF 12" APPLE TREE
- S75°E 104.2' SET NAIL AND TAG IN S.W. FACE OF 8" TRIPLE ASH

APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 345 of 1990

James G. Knapp
 CHAIRMAN
 DATE Nov. 14, 1997

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND SINGLE BIT AXE HEAD, ALONG SIDE A 10" X 10" STONE, BURIED 6" BELOW ROAD SURFACE, 2' NORTH OF CENTER OF 6 MILE ROAD (22' GRAVEL), AND IN LINE WITH STUMP FENCE ROW - SOUTH, AND 64' WEST OF OVERHEAD ELECTRIC TRANSMISSION LINE.

MEASURED DISTANCE TO C-01, T13N-R07W = 2641.78 FEET.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-01 - NORTH 1/4 CORNER, SECTION 5, T13N-R07W.
 FOUND SINGLE BIT AXE HEAD, ALONG SIDE A 10" X 10" STONE, BURIED 6" BELOW ROAD SURFACE, 2' NORTH OF CENTER OF 6 MILE ROAD (22' GRAVEL), AND IN LINE WITH STUMP FENCE ROW - SOUTH, AND 64' WEST OF OVERHEAD ELECTRIC TRANSMISSION LINE. REMOVED THE SINGLE BIT AXE HEAD, AND PLACED IN THE SAME POSITION, ALONG SIDE A 10" X 10" STONE, A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, BURIED 8" BELOW ROAD SURFACE, AND WITNESSED:

SET 60g SPIKE W/REMONUMENTATION TAG IN SOUTH SIDE OF 30" MAPLE	AZ. 84°	136.52 FEET
FOUND NAIL WITH TAG NO. 21567 IN WEST SIDE OF 14" MAPLE	AZ. 200°	30.10 FEET
SET 60g SPIKE W/REMONUMENTATION TAG IN S.E. SIDE OF 20" WHITE PINE	AZ. 226°	111.17 FEET
FOUND NAIL WITH TAG NO. 21567 IN N.W. SIDE OF 12" APPLE	AZ. 240°	38.95 FEET

Signed by *James G. Knapp*
 Surveyor's Michigan License No. 25853

Date NOVEMBER 24,



101 59 10