

MECOSTA COUNTY REMONUMENTATION PROGRAM

OCT 26 1999

CORNER APPROVED BY PEER GROUP ON FEBRUARY 13, 1998

STATE OF MICHIGAN COUNTY OF MECOSTA RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'99 JUN -1 P3:45

SECTION

For corners in MECOSTA (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T 13N R 08W	C-01
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

Joan Brown
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, JAMES G. KNAPP, in a field survey on MAY 20, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST ON NOV. 30, 1838, CORNER POST PLACED 40.24 CHAINS (2655.84 FEET) FROM 1/4 CORNER COMMON TO SECTIONS 5 AND 6, AND BEING 14.24 CHAINS (939.84 FEET) NORTH OF BROOK 20 LINKS, COURSE - S.E., AND NOTED: HEMLOCK 10" IS POST

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, DATED NOV. 29, 1929, NOTES: SEC. COR ON TOWN LINE AT STATION 41+70, 1/4 CORNER SECTION 5 AND 6, AT STATION 15+73, AND CENTER OF SHINGLE BOLT CREEK AT STATION 36+88, AND WITNESSED: F.P. EAST 21.7' F.P. S.W. 32.2'

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, BY W. H. WRIGHT, DATED APRIL 25, 1938, NOTES CORNER AS, "IRON STK.", AND BEING AT STATION 0+0, AND NORTH 1/4 CORNER SECTION 6, AT STATION 26+40, AND CENTER OF SHINGLE BOLT CREEK AT STATION 6+77.

CORNER NOTED IN P.A. 132 SURVEY AS RECORDED IN LIBER 11, PAGES 638 - 639, BY JAMES J. KELLER, P.S. 10693, ON MAY 5, 1993, AS, "FOUND 1/2" REBAR & CAP 4" DEEP", AND SHOWS A DISTANCE OF 2642.98' TO EAST 1/4 CORNER, SECTION 6, AND WITNESSED: NAIL 6" POPPLE N78°E 33.70' 2" IP POST 30" HIGH S39°E 40.50' TELEPHONE BOX S57°W 42.90' 2" POPPLE N64°W 41.24' 1/2" REBAR WEST 11.88'

APPROVED BY MECOSTA CO. PEER GROUP IN ACCORDANCE WITH P.A. 345 of 1990

James G. Knapp
CHAIRMAN
DATE FEB. 13, 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 1/2" RE-BAR, 3" BELOW GRAVEL ROAD SURFACE, 5' EAST OF CENTER OF 110TH. AVENUE (22' GRAVEL), AND IN LINE WITH 12 MILE ROAD (10' TRAIL - WEST, AND 12' NORTH OF 10' TRAIL - EAST), AND BEING 473' NORTH OF LEFT BANK OF SHINGLE BOLT CREEK.

SET MONUMENT AND HIGHWAY MONUMENT BOX DURING BITUMINOUS PAVING ON MAY 6, 1998, CORNER IS NOW 5.2' EAST OF CENTERLINE OF 110TH. AVENUE (21' BITUMINOUS).

MEASURED DISTANCE TO C-02 = 2643.11', AND TO C-11, T14N-R08W = 5142.73'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 C-01 - SECTION CORNER COMMON TO SECTIONS 5 AND 6, T13N-R08W.

FOUND 1/2" RE-BAR 3" BELOW GRAVEL ROAD SURFACE, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

PLACED A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT OVER THE 1/2" RE-BAR, INSIDE OF A HIGHWAY MONUMENT BOX A WITNESSED:

FOUND NAIL WITH TAG NO. 30104 IN N.W. SIDE OF 10" ELM	AZ. 38°, 48.12 FEET
FOUND NAIL WITH TAG NO. 30104 IN S.E. SIDE OF 14" MAPLE	AZ. 248°, 66.18 FEET
CORNER OF SECTIONS 31 AND 32, T14N-R08W (COUNTY MONUMENT)	AZ. 270°, 11.88 FEET
FOUND NAIL WITH TAG NO. 30104 IN N.E. SIDE OF 6" MAPLE	AZ. 324°, 56.14 FEET

Signed by James G. Knapp Date NOVEMBER 16,
 Surveyor's Michigan License No. 25853

FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS
 REVISED JAN. 1998
 ADAPTED FOR WORD PROCESSING MARCH 1998

