

MECOSTA COUNTY REMONUMENTATION PROGRAM

CORNER APPROVED BY PEER GROUP ON JUNE 13, 1997

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

JUL -2 11:35
1997

For corners in
 MECOSTA (County) Located In: Corner Code #

1. Public Land Survey	T 13N R 08W	C-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Joanne Brown
 Register of Deeds
 Mecosta County

Register of Deeds Stamp & File Number

I, JAMES G. KNAPP, in a field survey on JUNE 9, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

NOTE: Only one corner may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 DEPUTY SURVEYOR, NOAH BROOKFIELD, SET POST IN 4th QUARTER 1838. CORNER POST PLACED 40.00 CHAINS (2640 Feet) FROM CORNER COMMON TO SECTIONS 29, 30, 31, AND 32, AND WITNESSED: BIRCH 8" S37°W 47 LINKS (31.02 FEET)
 BEECH 8" N71°W 10 LINKS (6.60 FEET)

ON JUNE 4, 1903, DON B. ROBEN, COUNTY SURVEYOR, NOTES FROM FIELD BOOK No. 6, PAGES 28 AND 29, NOTES CORNER AS, "OLD STONE COR. GOV. WITNESS, SET IRON".

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, BY D. L. FOSTER, ON FEB. 19, 1919, SHOWS A DISTANCE OF 5215' FROM THE WEST 1/4 CORNER 30.

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, BY D. L. FOSTER, IN APRIL, 1921, SHOWS A DISTANCE OF 5206.3' FROM THE 1/4 CORNER COMMON 28 AND 29, AND WITNESSED: T.P N4°30'W, 29.8'.

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, BY W. H. WRIGHT, C.E. IN NOV. 1939, NOTES 1/4 AT STATION 372+91.4 AND NOTES CORNER AS, "IRON STAKE", AND THE WEST 1/4 CORNER OF SECTION 30 AT STATION 320+57.8, AND THE EAST 1/4 CORNER SECTION 29 AT STATION 425+28.2.

CORNER CALLED FOR IN UNRECORDED SURVEY (JOB No. 85028), BY DUANE F. WOOD, P.S. 24625, DATED MARCH 18, 1985, AND NOTES CORNER AS, "R.R. SPIKE IN CENTERLINE OF ROAD", AND WITNESSED:
 4" MAPLE S15°W 49.35
 SIGN POST S20°W 25.30

CORNER RECORDED AS PER P.A. 74, BY DUANE F. WOOD, P.S. 24625, IN LIBER 2, PAGE 198, ON DEC. 8, 1987, AND NOTED CORNER AS, "FOUND R.R. SPIKE IN CENTERLINE OF ROAD, ACCEPTED AS CORNER", AND WITNESSED:
 4" MAPLE S15°W 49.35
 SIGN POST S20°W 25.30

CORNER CALLED FOR IN UNRECORDED SURVEY (PROJECT No. 94709), BY BURT WICKHAM JR, P.S. 17639, DATED NOVEMBER 11, 1994, AND WITNESSED:
 4" MAPLE S15°W 49.35'
 SIGN POST S20°W 25.30'

CORNER CALLED FOR IN UNRECORDED SURVEY (JOB No. P-4472), BY BURT WICKHAM JR, P.S. 17639, DATED JUNE 27, 1995.

CORNER CALLED FOR IN UNRECORDED SURVEY (JOB No. 96429), BY WILLIAM G. TINGLEY, P.S. 30104, DATED SEPT. 17, 1996.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 1" X 1/4" FLAT IRON BAR ALONG SIDE OF 6" +/- SQUARE STONE, 32" BELOW BITUMINOUS ROAD SURFACE, 4' NORTH OF CENTERLINE OF JEFFERSON ROAD (22' BITUMINOUS), AND 5' WEST OF CENTER OF 110th AVENUE (TRAIL ROAD - SOUTH), AND 31' WEST OF FENCE LINE - SOUTH.
 FOUND RAILROAD SPIKE AS CALLED FOR IN L.C.R.C. LIBER 2, PAGE 198, AND USED BY WOOD, WICKHAM, AND TINGLEY AT AZ. 95°, 30.67 FEET

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 C-10 - 1/4 CORNER COMMON TO SECTIONS 29 AND 30, T13N-R08W.
 FOUND 1" X 1/4" FLAT IRON BAR ALONG SIDE 6" +/- SQUARE STONE, 32" BELOW BITUMINOUS ROAD SURFACE, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
 PLACED A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT OVER THE STONE, INSIDE OF A HIGHWAY MONUMENT BOX.
 SET 60d SPIKE W/REMONUMENTATION TAG IN S.E. SIDE OF 4" WHITE ASH AZ. 35°, 23.42 FEET
 RAILROAD SPIKE AS CALLED FOR IN L.C.R.C. LIBER 2, PAGE 198 AZ. 95°, 30.67 FEET
 EAST END OF 12" CSP CULVERT AZ. 145°, 37.29 FEET
 SET 60d SPIKE W/REMONUMENTATION TAG IN S.W. SIDE OF TW. 8" WHITE ASH AZ. 160°, 54.47 FEET
 WEST END OF 12" CSP CULVERT AZ. 200°, 32.07 FEET

Signed by James G. Knapp Date JUNE 15, 1997

Surveyor's Michigan License No. 25853 APPROVED BY MECOSTA CO. PEER GROUP

IN ACCORDANCE WITH P.A. 345 of 1996



LIBER **100** PAGE **238**

James G. Knapp
 CHAIRMAN
 DATE JUNE 12 1997