

**SURVEY & REMONUMENTATION**

JUL 10 1997

**MECOSTA COUNTY REMONUMENTATION PROGRAM**

COMMISSION

CORNER APPROVED BY PEER GROUP ON JUNE 13, 1997

LAND CORNER RECORDATION CERTIFICATE

JUL -2 11:34

Filing Requirement of Act 74, Mich. P.A. 1970

1997

For corners in  
MECOSTA  
 (County)

Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 13N R 08W C-13  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S T R  
 in Section S T R  
 3. Miscellaneous S T R  
 Property in Sec. S T R

4 Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

*Joanne Brown*  
 Register of Deeds  
 Mecosta County

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on MAY 20, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Only one corner may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**  
 DEPUTY SURVEYOR, JOHN HODGSON, SET POST IN JUNE 1837. CORNER POST PLACED 40.00 CHAINS (2640.00 FEET) FROM SOUTH 1/4 SECTION 32, AND WITNESSED: BIRCH 18" N40°E 10 LINKS (6.60 FEET)  
 HEMLOCK 20" N54°W 15 LINKS (9.90 FEET)

ON AUGUST 6, 1898, LYMAN W. JUNE, COUNTY SURVEYOR, NOTED IN COUNTY SURVEYOR'S RECORD BOOK NO. 1, ON PAGE 49, FROM FIELD BOOK NO. -, PAGES 172 AND 173, NOTES CORNER AS, "ORIGINAL OLD IRON COR. ONE O.B.T. STUMP".

ON JUNE 17, 1901, LYMAN W. JUNE, COUNTY SURVEYOR, NOTED IN COUNTY SURVEYOR'S RECORD BOOK NO. 1, ON PAGE 89, FROM FIELD BOOK NO. 4, PAGE 110, NOTES CORNER AS, "THIMBLE SKEIN 21 L. (LINKS) W. OF IRON PIPE".

MECOSTA COUNTY ROAD COMMISSION NOTES, CIRCA 1935, NOTES CORNER AS, "THIMBLE SKEIN".

APPROVED BY MECOSTA CO. PEER GROUP  
 IN ACCORDANCE WITH P.A. 345 of 1990  
*James G. Knapp*  
 CHAIRMAN  
 DATE JUNE 13, 1997

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
 FOUND 1/2" RE-BAR, 3" BELOW GRAVEL ROAD SURFACE AND AT 10" DEEP FOUND 3" DIA. TAPERED X 8" HOLLOW IRON (THIMBLE SKEIN). CORNER IS 2' NORTH OF CENTER OF EISENHOWER ROAD (22' GRAVEL), AND IN LINE WITH 110<sup>TH</sup> AVENUE (20' GRAVEL - NORTH), AND 15' WEST OF CENTER OF JOHNSON ROAD (20' GRAVEL - SOUTH).

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
 C-13 - SECTION CORNER COMMON TO SECTIONS 31 AND 32, T13N-R08W.  
 FOUND 1/2" RE-BAR 3" BELOW GRAVEL ROAD SURFACE AND AT 10" DEEP FOUND 3" DIA. TAPERED X 8" HOLLOW IRON (THIMBLE SKEIN), AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
 PLACED A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT OVER THE 1/2" RE-BAR, AND INSIDE OF THE THIMBLE SKEIN.  
 SET 60d SPIKE W/REMONUMENTATION TAG IN N.W. SIDE OF 12" BLACK ASH AZ. 27°, 65.60 FEET  
 1 1/4" WELL POINT (SECTION CORNER 5 AND 6 T12N-R08W) AZ. 97°, 14.45 FEET  
 N.W. CORNER OF HOUSE FOUNDATION AZ. 125°, 146.80 FEET  
 SET 60d SPIKE W/REMONUMENTATION TAG IN S.W. SIDE OF UTILITY POLE AZ. 319°, 39.46 FEET

Signed by James G. Knapp Date JUNE 17, 1997  
 Surveyor's Michigan License No. 25853

