

SURVEY & REMONUMENTATION

APR 04 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

For corners in
Mecosta

Located In:

Corner Code

#	(County)						
1.	Public Land Survey	Sec	T <u>13</u> R <u>10</u>	<u>E-9, Sec Cox</u>			
			T _____ R _____	_____			
			T _____ R _____	_____			
			T _____ R _____	_____			
2.	Property Controlling in Section	S _____ T _____ R _____	S _____ T _____ R _____	_____			
3.	Miscellaneous Property in Sec.	S _____ T _____ R _____	S _____ T _____ R _____	_____			
4.	Lot No. _____	Recorded Plat _____					
5.	Private Claims _____						

'95 DEC 29 A8:47

James Brown
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William Tingley a field survey on July 25, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1837, Abner VanNess, GLO Notes
Set Post Corner to Sections 20, 21, 28 and 29
Tamarack 6" N70°E 5 links
Tamarack 6" S42°E 3 links
- 1895, L.W. June, County Surveyor
Old Stake in Swamp
Tamarack 6", down and in place for Old Bearing Tree
- 1972, P. Salisbury, Notes from field
1-1/4" x 2" Pipe with "T" and Reducer
Maple 3" N14°W 26.60 feet
Twin maple 6-7" N43°E 33.10 feet
- 1981, Jack Pierson
1-1/2" Iron Pipe
Power Pole N48°W 20.30 feet
Triple Maple N67°W 112.25 feet
Maple Clump N14°W 83.40 feet
- 1989 Duane Wood, #24625, LCRC, Liber 2, Page 262
Found 2" pipe in road
Maple Clump N10°W 83.20 feet
Utility Pole N40°W 20.40 feet
Triple Maple 14" N45°W 112.10 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1-1/2" Pipe with "T" and reducer in swamp from above witnesses

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1-1/2" Pipe in Swamp. Replaced with remonumentation monument; left pipe beside monument.
- Nail and Tag in Power Pole N48°W 20.30 feet
- Nail and Tag in Triple Maple N67°W 112.25 feet
- Nail and Tag in Maple Clump N14°W 83.40 feet
- 10'-1" south of South Shoulder of Gravel Road

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 12-22, 1995
Surveyor's Michigan License No. 30104

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 345 of 1990
James M. Knapp
CHAIRMAN
DATE July 27, 1995

