

**SURVEY & REMONUMENTATION MECOSTA COUNTY REMONUMENTATION PROGRAM**

**CORNER APPROVED BY PEER GROUP ON FEBRUARY 12, 1999**

OCT 26 1999

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF MECOSTA  
RECEIVED FOR RECORD

**SECTION**

For corners in MECOSTA (County)	Located In:	Corner Code #
1. Public Land Survey	T 13N R 10W	E-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

99 APR 12 AM 4:43

*James Brown*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES G. KNAPP, in a field survey on APRIL 20, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Only one corner may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

DEPUTY SURVEYOR, JOHN HODGSON, SET POST IN JUNE 1837, CORNER POST PLACED 40.00 CHAINS (2640.00 FEET) FROM SOUTH 1/4 CORNER, SECTION 33, AND WITNESSED: PINE 18" N26°W 28 LINKS (18.48 FEET)  
W. OAK 12" N09°E 49 LINKS (32.34 FEET)

CORNER CALLED FOR IN COUNTY SURVEYOR'S BOOK NO. 1, PAGE 15, (FROM FIELD BOOK NO. 1, PAGES 48 THRU 49), BY L. W. JUNE, COUNTY SURVEYOR, DATED MAY 5, 1896, AND NOTED AS, "POST WITH GLASS", AND WITNESSED: PINE STUMP 20 N26W 28 = OBT  
PINE STUMP 24 N32E 100, AND BEING 39.96 CHAINS (2637.36 FEET) FROM EAST 1/4 CORNER, SECTION 32.

ROAD SURVEY NOTES AT MECOSTA COUNTY ROAD COMMISSION, BY W. H. WRIGHT, DATED NOV. 4, 1938, NOTES CORNER AS, "SEC. COR. IRON STR", AND BEING AT STATION 0+0, WITH SOUTH 1/4 CORNER, SECTION 32 AT STATION 26+47.5, AND WITH S.W. CORNER, SECTION 32, AT STATION 52+67.5.

CORNER CALLED FOR IN LAND CORNER RECORDATION CERTIFICATE OF CORNER E-1 OF T12N-R10W, MONTCALM COUNTY, BY SAMMY S. BARNETT, P.S. 16923 RECORDED IN LIBER 1, PAGE 73, ON APRIL 20, 1973, AS BEING, "9.90' EAST OF SE COR. SEC. 32, T13N-R10W".

CORNER RECORDED AS PER P. A. 74 OF 1970, BY DUANE F. WOOD, P.S. 24625, ON JUNE 14, 1979, IN LIBER 1, PAGE 483, AND NOTED AS, "FOUND 3/4" SQUARE STEEL BAR", AND WITNESSED:

**APPROVED BY MECOSTA CO. PEER GROUP  
IN ACCORDANCE WITH P.A. 345 of 1990**

12" OAK N70°W 46.22'  
P. POLE S75°E 78.68'  
18" OAK S75°W 61.88'

*James G. Knapp*  
CHAIRMAN  
DATE FEB. 12, 1999

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 3/4" X 16" IRON ROD, BURIED 13" BELOW GRAVEL ROAD SURFACE, AT 24" DEEP FOUND 1-1/2" X 1" X 16" TRIANGULAR BAR, (PUMP HANDLE), 14' WEST OF CENTER OF 220TH. AVENUE, (28' GRAVEL) AND 8' SOUTH OF EISENHOWER ROAD, (20' GRAVEL), CORNER IS IN LINE WITH 220TH. AVENUE FROM THE NORTH

MEASURED DISTANCE TO C-13 = 5261.26' AND TO F-13 = 2651.88'.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E-13, CORNER COMMON TO SECTIONS 32 AND 33, T13N-R10W.  
FOUND 3/4" X 16" IRON ROD, BURIED 13" BELOW GRAVEL ROAD SURFACE, AT 24" DEEP FOUND 1-1/2" X 1" X 16" TRIANGULAR BAR, (PUMP HANDLE), AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
REMOVED THE 3/4" X 16" IRON ROD, AND THE 1-1/2" X 1" X 16" TRIANGULAR BAR, (PUMP HANDLE), AND PLACED IN THE SAME POSITION A STANDARD MECOSTA COUNTY REMONUMENTATION MONUMENT, WITH THE IRON ROD AND PUMP HANDLE ALONG SIDE AND WITNESSED:

SET 60d SPIKE W/REMONUMENTATION TAG IN SOUTH SIDE OF 18" BLACK OAK AZ. 67°, 93.58 FEET  
FOUND 7/8" RE-BAR, CORNER COMMON TO SECTIONS 4 AND 5, T12N-R10W AZ. 90°, 9.91 FEET  
FOUND CEMENT NAIL IN NORTH SIDE UTILITY POLE AZ. 107°, 78.86 FEET  
FOUND NAIL WITH TAG NO. 16923 IN N.E. SIDE UTILITY POLE AZ. 144°, 89.65 FEET  
SET 60d SPIKE W/REMONUMENTATION TAG IN N.W. SIDE OF 8" JACK PINE AZ. 210°, 64.94 FEET

Signed by *James G. Knapp*

Date APRIL 8, 1999

Surveyor's Michigan License No. 25853



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JANUARY 14, 1975

REVISED JAN., 1983

ADAPTED FOR WORD PROCESSING MARCH, 1993