

SURVEY & REMONUMENTATION

APR 04 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

For corners in Mecosta (County) Located In: Aetna Township Corner Code # _____

1. Public Land Survey Sec 21 T 13 N R 10 W F-8, Center
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

'95 DEC 29 A 8:47

James Brown
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field surveyor on July 27, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:
 Not a GLO Corner.

- 1895, L.W. June, County Surveyor
 Old stake in Cast Iron Wheel 30"
 Pine Stump 18" N25-1/4°W 47 links
- P. Salisbury, Surveyor
 1/2" Iron Rod with cap
 Power Pole North 46.15 feet
 10" Black Oak N68°W 56.21 feet
 Concrete Monument S48°E 55.21 feet
- 1978, Duane Wood, #24625, LCRC, Liber 1, Page 457
 Found 1/2" Re-bar
 Poplar 10" N45°W 28.70 feet
 Poplar 6" N05°E 19.33 feet
 Poplar 8" S40°E 29.71 feet
- 1978 Duane Wood, Survey Liber Page
 Same record as LCRC
- 1981, Charles Fricke, #21781 as Recorded Liber 1, Page 457
 Same as Wood LCRC

APPROVED BY MECOSTA CO. PEER GROUP
 IN ACCORDANCE WITH P.A. 345 of 1990
James M. Knapp
 CHAIRMAN
 DATE July 27, 1995

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Reestablished corner at the intersection of quarter lines as established on 7-28-95 ratification of all quarter corners in Section 21 by Peer Group. This appears to be the best evidence for corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Remonumentation Corner set at intersection of 1/4 lines
 Concrete Monument S10°W 57.76 feet
 18" Oak N55°W 13.28 feet
 16" Oak N80°E 14.68 feet
 8" Oak S50°W 41.89 feet



This corner not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Signed by William G. Tingley Date 12-12, 1995
 Surveyor's Michigan License No. 30104